Can Creativity Be Reverse-Engineered? Language-model neurons as units of cultural inheritance in 80 years of Batman

Mike Taylor and Claude (Anthropic) · Version 2, draft of 9 November 2026

This is version 2 of the paper, in draft. Version 1 (20 October 2026) is unchanged in the repository. `CHANGES.md`, in the repository's `study/paper/v2/` folder, lists what changed and why.

Abstract

Memetics never had an agreed unit. A recent essay argues that most neurons in modern language models already have one main job [10]. That would make a neuron a ready-made unit: a meme is whatever makes a given neuron fire. Version 1 of this paper tested the idea on 32 Batman works from 1943 to 2022, with two small quantised models and a rule that counted any activation, however weak. This version repeats the study the way the essay studies neurons. The main model is Qwen3-32B at full precision. A unit is present in a work only where it fires strongly, at 30% or more of its strongest activation in about 48 million tokens of reference text. Explanations are written from the strongest examples and tested on new text, and steering and ablation are added. The plan was committed before the new models read a study text, and six tests were confirmatory.

One of the six passes. Heredity is supported: adaptations carry their documented source comic's units more than other comics' (15% of eligible comics beat the source, against 46% by chance; exact p = 0.0016), and the same holds in the three other models, in one of them with a failed positive control. Word counts find the sources at least as well (11%), and once word measures are regressed out nothing detectable is left in the units (p = 0.69). Version 1's hint that Llama's neurons add something beyond words came from a test that words alone can pass, and is withdrawn. Identity fails more plainly than before. Without names, Batman's canon does not tell Batman from other hero films (AUC 0.36, at or below chance, where a word-count score reaches 0.80), and version 1's name-free "superhero core" of seven units is down to one, and to none in the model version 1 used. The largest model, Llama 3.3 70B, scores higher on identity (0.77 on whole summaries and 0.65 on openings, both short of the bar). It is also the model that most often works out that a name-free summary is Batman's (29 of 32 works), so this test cannot tell a name-free identity from the model's recognition of the story. Selection is not detected. Steering fails on the study's units (17 of 126 idea units, 13%, against 20% by chance). On 40 neurons from the essay's gallery the same mechanism let a judge pick the right title 23 times, under an easier test. Switching off Batman's canon, about 212 units out of 3.3 million, lowers the model's recognition of Batman far more than matched random units do (2.39 against 0.02 in log-odds). That test is not evaluable, so it is not counted as a pass: five of the 32 untouched replies did not begin with a name, one more than allowed by a rule added to the plan before any reply had been seen. In Qwen3-8B, where the test could be evaluated, the effect was not specific to Batman. A follow-up test was written after those results were seen and fixed in the plan before it was run. It applies the same criterion to the same texts and units, with the model's reply already begun with "Answer:", so that the next word the model writes is the name. It is met in Qwen3-32B and not met in Qwen3-8B. In Qwen3-32B the fall is 1.81 against 0.03 for the random units, other heroes' names do not fall on average, and one reply of 32 does not begin with a

name. That was the expected outcome, and because the texts and units are the same it is not independent evidence. The test as first registered stays not evaluable. In Qwen3-8B the effect is again not specific to Batman.

The same method was then run on two further corpora, under a second plan committed before any model read them as study works. On Sherlock Holmes (81 screen works, the 60 stories and 229 detective films), heredity holds again, for units and for words: 3% of the stories rank above an adaptation's documented story, against 44% by chance. Identity comes closer than on Batman and is not established. Without names, the canon tells the screen works from detective films of their era at an AUC of 0.77 in Qwen3-32B, short of the bar of 0.80. In Llama 3.3 70B, a replication model, it reaches 0.90 and meets all six clauses of the test. In both models the score follows what the model can name (0.81 for the works Qwen3-32B names and 0.53 for the rest), so recognition is again not ruled out. Selection is again not detected, by a test with one chance in three of detecting it. On 220 pairs of an Indian film and its remake in another Indian industry, a model built from 18 word measures ranks the documented source first for 205, and its remaining doubt is worth about 21 pairs. In those pairs the units lean towards the documented source. The test's score, Z, is 3.45. None of 2,000 runs with pure noise in the units' place reaches that score, and none of the 406 word-only measures tested beforehand does. A simple sentence embedding put through the same test scores 0.85. This is the study's first evidence that neurons carry information about a story's source that these word measures miss, and it met all seven conditions set for it in advance. It comes with limits. The test controlled for words only: the year of release, put in the units' place, also scores above every word-only stand-in, and the units were checked against it only afterwards (Z = 3.04 with the year and five other properties controlled). Its calibration condition was met at the margin. A word measure built afterwards, which leaves out the characters' names, scores as high as the units in their place (3.48); with it and every other measure built in that check added to the word model, the units still score 3.43, with about half of the gain. The two 8B models agree, on the same pairs. The largest model agrees only for films it recognises. The effect rests on a few families of films, most of it comes from sources whose summaries were part of the corpus that set the units' scales, and adding the units puts the documented source first for one more pair (206 of the 220 against 205).

What improved is the unit itself, as a thing that can be described. In a secondary check, descriptions of 241 units chosen by rule predict where the units fire in short texts written to fit them: 81% of new examples and 3% of near misses fire strongly. The essay reports 76% and 11% for its own gallery, with a stricter scale and a fuller procedure, so the two are not directly comparable. 46% of the units still fire when the description is put without its key words. In ordinary plots, near the threshold that decides presence, a description accounts for about half of a unit's firings. By a blind judgment the canon is mostly names, places and words (38 of the 60 core families that were explained), and much of the rest is the comic-book register. So a neuron can be named and the name can be tested against what the neuron responds to, which version 1 could not claim. The name is not yet supported by what the neuron does, because steering failed. On Batman none of this makes a neuron a better unit of inheritance than a word. On the remakes the neurons add something to the word measures and do not replace them. Whether they still do so for films that no model has read, and whose summaries set no unit's scale, is open, and the test that would settle it is not yet registered. A different experiment, on new stories whose wording is changed on purpose, is written up as a pre-registration in the repository and has not been run.

1. Introduction

Cultural evolution borrowed the gene's logic but never found its gene. Dawkins proposed the meme as the unit of cultural inheritance in 1976 [1], and the idea spread faster than any method for testing it. Two decades later the field's own stock-take asked whether memetics was a science at all [2]. The recurring answer was that no one could say where one meme ends and the next begins, so no one could count memes, track their copying, or measure their fitness [3]. Heylighen and Chielens review the field [17]. Cultural evolution research moved on without the unit, studying traits that could be coded by hand [4].

This study began with a recent claim from interpretability research. In "Neural networks are already clean", Cammarata argued that most neurons in modern language models such as Qwen3 already have one main job, often as specific as a feeling or a narrow trope, and that the apparent mess of earlier models came from fixable training and tooling problems rather than from superposition [10]. If that is right, a neuron is a ready-made, inspectable and testable unit, and memetics has the definition it lacked: a meme is whatever makes a given neuron fire. The rest of this introduction sets out why such a unit is needed, what it has to beat, and what the first version of this paper found.

The obstacles are specific. Concepts like "Batman" lack objectively measurable properties, and people hold different versions of them [16], so there is no agreed place to look for a "Batman meme" and no way to check that two people carry the same one. Members of a meme family such as the Scarlet Pimpernel, Zorro, Batman and Iron Man differ in more ways than they agree, so rule-based coding struggles to group them. Without a rigorous definition, memes cannot be categorised at scale, used for testable predictions, or measured without slow and error-prone human labelling. In that sense memetics is still pre-Mendel: no one has traced the inheritance of thousands of memes.

Hand-coded traits have carried that work a long way. Tehrani reconstructed the family tree of Little Red Riding Hood from coded plot features [5], and da Silva and Tehrani coded which international tale types each of 50 Indo-European populations tells, then used comparative phylogenetic methods to trace some tales to the Bronze Age [6]. The trait list in those studies comes from folklorists' indexes. It is reliable and expert, but it is fixed in advance, coarse, and costly to extend to a new body of stories.

Other work traces inheritance from the words themselves, with no hand-coded list. Barbrook and colleagues built a family tree of the manuscripts of *The Canterbury Tales* from their copying variants [21]. Chavalarias and Cointet rebuilt the branching lineages of scientific fields from the terms their papers share, and called the result phylomemetic [19]; this project uses the same word for a different method. Kuhn, Perc and Helbing found scientific memes, words and phrases that are inherited along citation links, with no linguistic knowledge [20]. In stories, film remakes can be matched from their Wikipedia plot summaries [22], and summaries of the same story become much harder to match once their names are replaced [23]. Word-based units like these are automatic too. So the question for any new unit is what it finds that words miss.

Language models offer a candidate unit that is neither fixed in advance nor hand-coded. Interpretability research has found single neurons that respond to one concept across many surface forms, including a Spider-Man neuron in CLIP that fires for photographs, drawings and the written name [7], much like the concept cells recorded in the human brain [18]. Neurons with similar jobs recur across separately trained models [8], and different models' representations appear to converge as they scale [9]. Text embeddings from different models can even be translated into one another without any paired examples, which suggests a shared geometry of meaning [27]. Automatic descriptions now exist for every MLP neuron of Llama 3.1 8B Instruct [24], one of the models used here, and features learned

from text embeddings have been used to find and name the properties of texts that predict an outcome [25]. Cammarata's claim that most such neurons are already clean [10] is what would make them usable as a list of traits.

We test that proposal first on one long, well-documented lineage: Batman, from the 1943 film serial to The Batman (2022), alongside literary and superhero relatives from Puss in Boots (1697) to The Green Hornet (2011). Batman is a convenient model organism. Its lineage is long and branching, many works state their sources, and fans and critics have argued for decades about what is and is not canon.

We ask three questions, matching the three things a science of memes needs. Identity: is there a set of neuron-defined memes that a story must carry to be Batman, and does it survive when every name is removed? Heredity: do adaptations carry the optional memes of their documented source comics more than those of other comics? Selection: do memes carried by popular early works spread further into later ones? Alongside these we ask whether the units respond to ideas or only to particular words, whether they find anything that plain word overlap does not, and whether the model uses them.

What version 1 found. The first version of this paper (20 October 2026) ran the study on Qwen3-8B and Llama 3.1 8B, with weights quantised to 4 bits, on a laptop. Adaptations carried their source comic's units more than other comics', so heredity was supported, but plain word overlap found the sources as well. Without names the canon could not tell Batman from other masked heroes. Most of the strongest units detected names and words, and selection was not detected.

That version's method left several things open. Its limitations section named two: the models were smaller than the 32B model the essay studies, and quantised, and the labels had never been validated by steering. Others became clear afterwards. A meme counted as present in a work whenever the work beat 68 of 69 ordinary films, so a weak activation counted as much as a strong one, where the essay's point is that the strong ones are what matter. The labels were read off the Batman corpus itself. Nothing was tested by ablation.

What this version changes. This version re-runs the study the way the essay studies neurons. The main model is Qwen3-32B at full precision. Only a unit's own sign regime counts. A unit is present when it fires strongly: at least 30% of the strongest activation it reaches anywhere in a broad reference corpus. Explanations are written from the strongest examples in that corpus and then tested on new texts, where they can lose. Steering tests the labels, and ablation tests whether the model uses Batman's canon to know it is reading Batman. The corpus, the three experiments and their word-based comparators are those of version 1. Section 3.1 reports what the change of method did to each of version 1's conclusions.

Two more corpora. One franchise of 32 works could not settle several of these questions, and the first draft of this version said so. The same method was therefore run on two further corpora, built by rule from Wikipedia and analysed under a second plan that was frozen before any model read them as study works: the Sherlock Holmes stories with 81 screen works, and 220 pairs of a film and its remake. Sections 2.11, 3.11 and 3.12 report them. On Holmes, heredity holds again and identity comes closer without being established. On the remakes, for the first time in this project, the units carry information about a story's source that the word measures miss.

2. Material and methods

The analysis plan for this version is `study/v2/PLAN.md` in the repository. It was committed and pushed before any of the new models read a study text. Section 18 of the plan logs thirty-five entries made after that, each with its reason and with what was known at the time. Section 2.10 lists the ones that matter for reading the results.

2.1 Corpus

The corpus is unchanged from version 1. We used the plot sections of English Wikipedia articles, keeping the first 40 sentences of each. These retellings were written by people. The lineage comprises 32 Batman works from 1943 to 2022: 13 live-action films and serials, 12 comics, 4 animated films and 3 video games. The comparison set has 13 relatives. Five are literary ancestors: Puss in Boots, The Count of Monte Cristo, A Study in Scarlet, Dracula and The Scarlet Pimpernel. Eight are masked-hero or superhero films: The Bat (1926), The Mark of Zorro (1940), The Shadow, Superman, Spider-Man, Daredevil, Iron Man and The Green Hornet. There are also 69 popular films with no superheroes. In version 1 those films set the bar for every meme. Here they are 69 more ordinary stories. The corpus has 3,700 sentences.

The name-free version of every text is also unchanged: each proper name is replaced by a neutral code (X1, X2 and so on, consistent within a work). Two things about these texts are handled differently.

- **Codes.** The codes are our edit and not part of the story, and their numbers differ by work. In version 1 the bar for a name-free text came from name-free films, which have codes too. Here the bar comes from ordinary text without codes, so a unit that reacts to a code would look rare and specific. A code's own tokens are therefore not allowed to carry a unit's peak. Scores with the codes left in are kept as a check.
- **Length.** A unit's score is a peak over sentences, so a longer text has more chances, and Batman's summaries are longer than the hero films' (sentence count alone separates them with an AUC of 0.76). Every score is therefore also computed on each work's opening: its first sentences, at most 20 and at most 400 words, which leaves Batman works and hero films the same length (AUC 0.45).

2.2 Models and units

The main model is Qwen3-32B [11], the model the essay studies. Qwen3-8B is the same family at a quarter of the size, and is the model version 1 used. Llama 3.1 8B Instruct [12], from a different company, was version 1's replication model, and Llama 3.3 70B Instruct is that company's model at large scale. All four ran in PyTorch at the precision of their published weights (16-bit floating point) on rented GPUs. Version 1 ran the two 8B models with weights quantised to 4 bits.

A neuron is one channel of a feed-forward block: the product of a gate and a value, which feeds the block's output projection. Its positive and negative extremes are separate units, as in version 1 and in [10]. That gives 3,276,800 units in Qwen3-32B, 884,736 in Qwen3-8B, 917,504 in Llama 3.1 8B and 4,587,520 in Llama 3.3 70B. New in this version, an activation counts only where the gate is open. Where the gate is closed the product is a small echo of the opposite sign, which the essay shows to be a different signal from the unit's own. Each text was read as one continuous document, and the first position of a document is ignored.

To check the extraction, we compared our activations with the ones the essay publishes. For 63 Qwen3-32B neurons in layers 0 to 12 the essay gives 756 example contexts with the activation at a marked token. Ours correlate with the published values at r = 0.992.

2.3 Scale, presence and base rate

Scale. The essay calls a response strong when it reaches 30% of the neuron's strongest example in a large corpus. We measured each unit's strongest activation over a reference corpus of 46,000 documents (about 41 million tokens): 12,000 film plots, 24,000 English Wikipedia articles and 10,000 passages from books. English prose alone would understate the maximum of a unit whose real job is code, chat or another language, so a supplement of 5,434 documents (about 7 million tokens) adds source code, conversations with an assistant, Wikipedia in ten other languages, news and reviews. A unit's scale is its strongest activation in the reference corpus, the supplement or the study's own original texts.

Presence. A unit is present in a work when its strongest activation in any sentence of the work is at least 30% of its scale. Version 1 asked instead whether the work beat 68 of 69 reference films, so any activation counted, however weak.

Base rate. Three thousand of the film plots, cut to 40 sentences like the study's works, serve as the background of ordinary stories. A unit's base rate is the share of them in which it is present. One turned out to be a study film under an older title and was left out, which leaves 2,999. A unit is distinctive when its base rate is at most 3%, the rate at which an ordinary film crossed version 1's bar.

Which units enter which analysis. The canon, the identity experiment and most of the units chosen for explanation use distinctive units, because there the question is what marks Batman off from ordinary stories. The heredity and selection experiments use every unit, as version 1 did. There the question is which units two works share, and the word-based comparators drop no word either.

2.4 Memes, canon and other franchises

Candidate memes are distinctive units present in at least 6 of the 32 Batman works. Candidates that fire strongly on the same sentences (correlation of at least 0.5, average linkage) were merged into meme families, as in version 1. Canon tiers follow the number of Batman works a meme appears in: core (29 or more), common (23 to 28) and optional (6 to 22).

Version 1 compared Batman's canon with random sets of the 69 films. Under a 3% cap a random set of ordinary films cannot have a canon, whatever Batman is like. So this version adds comparisons that could fail: random sets of 32 background plots of one genre, and six other film series from the same plot dataset in which one character's name is in the title of at least 15 films (Godzilla, Frankenstein, Dracula, Doraemon, Tarzan and Kamen Rider).

2.5 Three pre-registered experiments

The designs, statistics and nulls are version 1's. E2, E3, the sequel control and the residual test are computed by version 1's own code on the new presence data. These are the same 32 works, analysed a second time by a method fixed in advance, with version 1's outcome known. Agreement between the two versions is therefore not independent confirmation.

E1, identity. For each Batman work, canon units are distinctive units present in at least 80% of the other 31 works (original texts). The held-out work is scored by the share of canon units present in its name-free text, and compared with the 8 masked-hero and superhero films. The prediction is met if the AUC is at least 0.80, its bootstrap 95% lower bound is at least 0.65, it is above the 95th percentile of a label-shuffle null, it holds within 0.05 after dropping sentences with iconography words, and, on the openings, it is at least 0.70 and above its own label-shuffle null. The last clause is new: without it a pass could be a matter of length. It is falsified, as version 1 registered, if the AUC is below 0.70 or its interval includes 0.5.

Version 1 put its failure on E1 down to the scoring rule, because a word-based centroid score reached 0.80 where the canon share reached 0.52. So the units are also given the words' rule: the cosine between a work's vector of strong unit activations, each weighted by the unit's rarity in the background plots, and the centroid of the other 31 works. The same criteria are applied to that score, to the TF-IDF centroid and to length alone.

E2, heredity. Nine adaptations have a documented source comic among the 12 comics. Optional units are those present in 2 to 16 of the 32 Batman works (name-free texts). For adaptation A and comic C, the inheritance rate is the share of C's optional units also present in A, z-scored against the same rate in the 11 Batman screen works that adapt no comic. The statistic is the share of eligible comics that beat the documented source, averaged over the adaptations. It is tested exactly, over all 3,991,680 ways of rela-

belling the comics. The prediction is an exact p below 0.05. The positive control is that at least 5 of 7 sequels rank their prequel among the top two earlier screen works. The word comparators (TF-IDF cosine and word presence on the same name-free texts) go through the same test.

Beyond words: the residual test. Whether the neurons add anything beyond shared words is decided by one test: the neuron inheritance rate with word measures regressed out, tested the same way. Version 1 regressed out two word measures. Before any Qwen3-32B result existed, two reviewers showed with words alone that this form can pass with nothing beyond words in it: a third word measure that leans towards commoner words, or counts repeats, passes it in the neurons' place ($p = 0.002$ and 0.0002). The decision test therefore regresses out seven word measures: version 1's two, word presence in four bands of frequency, and TF-IDF on raw counts. Fifteen further word-only measures were then put through it in the neurons' place. None passes (lowest $p = 0.12$), where seven of the fifteen pass version 1's form. "The neurons add something beyond shared words" is claimed only if the decision test passes at the primary setting and in at least half of eight sensitivity settings, and a version with every word and code measure regressed out passes too. Version 1's two-measure form is reported beside it.

E3, selection. Unchanged: across the 15 Batman works before 2000, the rank correlation between log pageviews and the spread of a work's units into the 9 later works that adapt no comic. With 15 works the test has about 27% power against a true correlation of 0.3, so this version makes no claim about selection whatever the result.

Recognition. A 32B model has read these Wikipedia summaries. Given a name-free one it may simply work out which story it is. So each model was asked, for each name-free text, which famous fictional hero the story is about and which work it summarises, and the experiments are read against its answers.

2.6 Explaining units, and letting the explanations lose

Version 1 named its memes from eight sentences of the Batman corpus itself. Here the units to explain were chosen by rule, before anyone read an example, in eight sets:

- *core*: the representative of every core-canon family, up to 60;
- *common* and *optional*: 30 families drawn at random from each of those tiers;
- *name-free core*: canon units still present in at least 70% of the name-free Batman works, up to 40;
- *discriminators*: the 40 distinctive units that best separate name-free Batman works from the hero films;
- *common story patterns*: the 40 units with a base rate between 3% and 30% that are most over-represented in Batman works, which the 3% cap would otherwise hide;
- *inherited* and *not inherited*: 20 units drawn at random from E2's optional units that an adaptation shares with its source, and 20 from the rest.

The same rule was applied to Qwen3-8B. Each role below was played by AI agents (Claude) that saw nothing but their own prompt. The prompts are in `study/v2/prompts/`.

- An *explainer* read each unit's 16 strongest examples from the reference corpus and supplement, the first six with their whole document up to the peak, its 8 strongest study sentences, and the strongest examples of its opposite pole. It wrote a title, a short explanation and at least 8 key words. It ran no experiments.
- A *tester* saw only the title, explanation and key words. Before anything was measured it wrote five new texts that should make the unit fire (A), five that should make it fire while using none of the key words (B), five near misses that should not fire, at least three of which reuse a key word in another sense (C), five on a distant subject (D), and one meant to fire it as hard as possible.

- A *keyword analyst* saw only the title and explanation and wrote the search terms of someone who expects the wording to be evaded.
- A *kind judge* saw only the title and explanation. It said what kind of thing the unit detects, and whether it reacts to a particular name or word or to an idea that can be put in other words.

A text's response is the unit's strongest activation in it as a share of its scale, and 30% or more is strong, as in the essay. An explanation *wins* when more of its A texts than of its C texts are strong. A unit is *idea-bound* when at least 3 of its 5 keyword-free texts are strong and at most one keyword-reusing near miss is. Every text was scored on every explained unit, which gives the rate at which a unit fires strongly on texts written for other units. Two word-based measures were scored on the same texts: the analyst's search terms, and TF-IDF similarity to the unit's examples.

Test texts are short and read alone, while a unit's scale comes from documents of about 1,000 tokens. A unit whose own strongest study sentence and strongest reference examples all stay below 30% when read alone is counted apart, as *not testable out of context*. A coverage check asked a blind judge whether each description predicts the unit's firings at 30 to 60% of scale, where presence is decided, on passages from the background plots.

This is label validation. It is not the planted-story test that the planned pre-registered experiment reserves for the question of whether neurons follow an idea when the words change (Section 4.5).

2.7 Steering and ablation

Neither test was in version 1. Both were specified in the plan before being run.

Steering. The model continued three neutral story openers for 40 tokens with one unit's activation held at a multiple of its scale, and once without. A blind judge who saw both sets of continuations picked which of five unit titles had been pushed in, or "none of these". The multiple was chosen beforehand on 40 neurons from the essay's public gallery, not on study units. The criterion is accuracy on the units whose kind is an idea, against 20% chance.

Ablation. Each model was asked which hero each name-free Batman summary is about. The outcome is the log-odds that its reply starts with Batman's name, with nothing touched and with that work's canon units switched off on the tokens of the summary only. The canon's effect is compared with two controls of 200 random sets each. In the first, every canon unit is replaced by a unit of the same layer and pole that is present in about as many name-free Batman works. In the second, the replacement is also matched on how strongly it fires in these texts. Those sets still remove less activation than the canon does, so the effect is also given per unit of activation removed. The criterion needs p below 0.05 against both controls, and a larger effect on the Batman works than on seven hero films scored on their own hero's name. Because the score is the probability of the reply's first word, the test counts only if the untouched model's reply begins with a name for at least 28 of the 32 Batman works.

A follow-up to the ablation. The registered ablation of Qwen3-32B turned out not to be evaluable (Section 3.8). After seeing that, we fixed one follow-up test in the plan and pushed it to the repository before Qwen3-32B or Qwen3-8B had read any text with a begun reply. The question is the registered one, word for word, and the model's reply is begun for it: the reply already starts with a fixed prefix when the model begins to write, so that the next word it writes is the name. The texts, each work's canon units, the random sets and the criterion are those of the registered run, including the rule on how the untouched replies begin. A begun reply counts as beginning with a name only if the model goes on with one space and then a name, because the score reads the name only in that place. The prefix was chosen by a rule in the same plan entry, so the rule was fixed before any begun reply existed. The rule reads only the form of the replies, on texts outside the test and with nothing switched off. The 69 ordinary

films were put to the untouched Qwen3-32B with the reply begun "Hero:", and a prefix was to be used only if at least 62 of the 69 replies began with a name. If "Hero:" failed, "Answer:" was to be checked once in the same way, and if that failed too the follow-up was not to be run. "Hero:" failed with 48: after it the model wrote the name in bold for the other 21. "Answer:" passed with 65 and was used for both models. The result of the check was committed before any ablation job was scored. Neither model read a Batman work or a hero film with "Hero:", so there is no ablation result under that prefix, and we do not know what it would have been. The follow-up is not one of the six confirmatory tests. It reads the same model, texts and unit sets as the registered run and was written knowing that run's numbers, so it is not independent evidence.

2.8 Two models

For each explained Qwen3-32B unit, its twin in another model is the unit there whose activations across the 3,700 original-text sentences correlate most strongly with it. Version 1 scored twins on those same sentences and on their name-free versions. Here they are scored where they were not chosen: on the tester's texts written for the Qwen3-32B unit, and on the name-free sentences. On the name-free sentences they are compared with other Qwen3-32B units, matched on how well a single word predicts them, and those units' own twins.

2.9 What is confirmatory, and robustness

Six tests are confirmatory, all for Qwen3-32B under the new rule: E1, E2, the residual test, E3, the ablation and steering on idea units. Each is read at 0.05, with Holm-adjusted p values beside them. The other three models are replications. Everything else is description or a sensitivity check, except the follow-up test of the ablation (Section 2.7), which was written after the registered result was seen and is not confirmatory.

The sensitivity checks were fixed in advance. They vary the threshold (20, 30, 40 and 50% of scale), the score (strongest sentence or the mean of the three strongest), the base-rate cap (1% to 30%, or none), the scale (without the study texts; the fifth-strongest example in place of the strongest), text length (openings), the handling of the codes, the echo regime, weak poles and units whose scale comes from the supplement. To separate the effect of the new rule from the effect of the new models, every primary statistic was also computed under version 1's rule on the new activations.

2.10 Changes after the plan was frozen

The plan logs thirty-five entries. The last points to the plan of the two further corpora (Section 2.11), which has a change log of its own. Most of the changes were made before the result they bear on existed. These are the ones that change how a result is read.

- The residual test regresses out seven word measures, not two (Section 2.5). Its sensitivity rule uses the eight settings with no base-rate cap, because a cap applied to units and not to words can make the test pass or fail for reasons unrelated to the question.
- The ablation has a second control matched on how strongly the units fire. It is scored in log-odds, because a fall in log-probability shrinks as the model grows confident. It counts only if the untouched replies begin with a name (Section 2.7).
- Genre sets take their base rates from plots of other genres.
- A whole-work E1 score is always quoted with its opening-only score and with length alone.
- A count of model-by-rule cells below 0.05 is reported against a joint null, because the cells share the same 32 works. This was decided after the two 8B models' results were in and before any Qwen3-32B result.

Besides that one, five changes were made after a result had been seen. None changes the outcome of a registered test, and one adds a test. The coverage judging was repeated, because the item ids in the first round told the judge the answer. The first round's tally had been seen (54.5% of firing passages covered, 2.9% of silent ones wrongly claimed), and the blind round gives 48% and 3%. The rule that decides whether a reply begins with a name treated "The Joker" as a sentence. It was corrected after Qwen3-8B's ablation had been scored, and the outcome is the same for both models under either form of the rule. A count of the placeholder codes in the name-free texts (Section 3.7) was added after the explanations had been read, as a description. A look at the Qwen3-32B ablation in the works whose replies begin with a name was added after that ablation had been scored, also as a description (Section 3.8). The change that adds a test is the follow-up ablation of Section 2.7. It was written after both models' registered ablations had been scored, and was pushed before any of its jobs was run.

One planned step, the re-scoring of version 1's rewordings (Section 3.7), had been missed. It was run after every other step of the registered plan, when the fact-check of this paper found the gap. Only the follow-up ablation was run later. Two things in the plan were not done. Two of the second-opinion checks in the review of the plan were cut short when the analysis machine restarted. For Llama 3.3 70B the sensitivity grid, the multiverse and version 1's rule were not run, for lack of time and of disk space on the analysis machine. Its results are for the primary setting only. The explanation tests and the ablation were run on the two Qwen models, and steering on Qwen3-32B alone.

2.11 Two more corpora

Sections 2.1 to 2.10 describe one franchise of 32 works. Section 4.4 lists what that could not settle: too few adaptations to tell units from words, too few negatives, too few early works, and a corpus that had already been analysed once. Two more corpora were built to address those limits: the Sherlock Holmes stories with the screen works made from them, and film remakes. Their plan (`study/v2/second/PLAN.md`) was committed and pushed on 8 November 2026, before any of the four models read a new text as a study work. The machines had been started half an hour before that commit, to run the checks on the Batman works, and the plan's log puts the first reading of a new text three minutes after it. Two texts of the Holmes corpus are also texts of the Batman study (A Study in Scarlet and The Bat), and many of the films are documents of the reference corpus (see *Scale and checks* below). The plan's Section 15 lists what had been run by then, all of it with words alone, on made-up data, or on texts the models had already read, and its Section 16 logs every change made afterwards. The units, the sign regime, the 30% rule and the statistics of E1, E2 and E3 are those of Sections 2.2 to 2.5. The background is the same plots less the 34 that are older summaries of films of the Holmes corpus, which leaves 2,965. None of the explanation, steering, twin or ablation tests was repeated.

Sherlock Holmes. Every text is the plot section of a work's own English Wikipedia article as it stood on 8 November 2026, cut to its first 40 sentences. There are the 60 stories of the Conan Doyle canon (4 novels and 56 short stories), 81 screen works, and 229 detective films that serve as negatives. The screen works are every page with a usable plot in three Wikipedia categories: Sherlock Holmes films, episodes of the television series Sherlock, and video games based on Sherlock Holmes. By kind of page they are 46 films, 9 television films or programmes, 13 episodes and 13 games. The detective films are every American or British film in the film table that the reference corpus was drawn from whose genre is given as mystery, detective or whodunit, and whose plot names neither Holmes nor Watson. What each screen work is based on was taken from its article and not from its plot. Two AI readers, who were shown no plot, wrote down each Conan Doyle story the article says the work adapts and how firmly it says so; they disagreed on two works, which a third reader read, and the majority decided. By that reading 22 screen works are adaptations of at least one story, 14 stories in all, and eight of the 22 are versions

of The Hound of the Baskervilles. Nine of the 22 are straight adaptations of a named story, 16 other works are said only to take elements from stories, and 43 state no source. Name-free texts were made by the procedure used for Batman (Section 2.1).

Film remakes. The films are those of the same film table: 34,070 Wikipedia pages with plots as they stood in 2017 and 2018. A pair is a film and the earlier film it remakes, as stated in the opening of either film's article today. Two AI readers, who were shown the page's title, the sentence and the films it links to, and no plot, decided what each of 1,693 such sentences says and whether its wording is firm; a third read the 9 they read differently. 482 pairs were kept, each with at least 15 sentences of plot on both sides, in 400 families of related films. A film is never a candidate source for a remake of its own family, and every test treats a family as one cluster. The primary set is the 220 firmly stated pairs in which both films are Indian and come from different industries, a Tamil film remade in Hindi for example. It was chosen before any model had read a film, as a homogeneous set of the films a model is least likely to know by heart. In 100 of the 220, at least a tenth of the remake's five-word sequences also occur in the source's summary, which we take to mean that the plot was pasted from one article into the other. Those pairs are kept and flagged as copied. Names are left in, because a remake in another language changes the names by itself, and the word measures see the same names the units see. Three models read 16,218 films, every film that could be a candidate source. Llama 3.3 70B read 3,926 of them: the 3,516 films of the Indian industries, which are all the primary set needs, and the other films of the pairs.

Scale and checks. A unit's scale is the scale without the study texts of Section 3.10: its strongest activation in the reference corpus and the supplement. It was fixed before any new text was read, so reading the new texts changed no unit's scale. It is not independent of them. The reference corpus was drawn from the same film table, so 479 of the 887 films of the remake pairs are among its documents (the source in 137 of the 220 primary pairs), and so are older summaries of 112 of the 310 screen works and detective films of the Holmes corpus. Their activations are part of the scale, which matters for how the remakes result is read (Section 3.12). Presence was stored as bits by a new pass. On each machine its first job was to reproduce the stored presence of the works of the Batman study for that model, and it did so in every bit for all four models. The counts each machine returned for the remakes were recounted on the analysis machine at the primary setting, for every remake against the 887 films of the pairs (417,777 counts for each model), and none differed.

The tests on Holmes are E1, E2 and E3 with the changes the corpus forces. In E1 the 81 screen works stand against the 229 detective films. The detective films are older than the franchise, so the AUC is taken within three eras (up to 1949, 1950 to 1999, from 2000) and averaged over the screen works. The six clauses and their thresholds are those of Section 2.5. In E2 the 60 stories are ranked for each of the 22 adaptations by the units they share with it. Each source story has one vote, so that the eight versions of The Hound count once. The null is 100,000 random relabellings of the 14 source stories among the 60, and each rate is z-scored against the same story's rate in the 43 screen works with no stated source, as in Section 2.5. The positive control asks that at least 7 of the 9 straight adaptations rank a story they adapt straight in their top two, by the unadjusted rate. In E3 the early works are the 60 stories and the later works are the 43 screen works with no stated source, with one more covariate than before: the number of screen works whose article names the story. Its power was computed beforehand as about 32% against a true correlation of 0.3, so the plan fixed that neither outcome would be read as a finding about selection. A residual test is reported for Holmes and is not confirmatory. Its form is stronger than that of Section 2.5: nine word measures, their squares and their pairwise products are regressed out. Before any model was run, 82 of 422 further word-only functions of those measures still passed it in the units' place, so a pass would not have meant what it should.

The tests on the remakes are two. *Heredity* asks whether the units find a remake's source among its candidates. Some films share units with almost every film. So, as in Section 2.5, each inheritance rate is first z-scored against the same candidate's rates with the other remakes; we call this the hub adjustment. For each pair the test then takes the share of the remake's candidates whose adjusted rate is above the documented source's. The shares are averaged within families and then over families, and the null is 10,000 random relabellings. For the primary set the candidates are the films of the Indian industries other than the remake's own that are not later than the remake and not of its family: 1,544 for the median remake. The confirmatory figure uses the 120 pairs that are not copied. The 100 copied pairs are the positive control: the source must rank strictly first in at least 90 of them.

The decision test asks whether the units add to word measures. Three statistician agents, working apart and with word data only, each designed and calibrated a replacement for the residual test, which cannot be trusted on this corpus either. The one with the best calibration and power was adopted before any unit existed.

It first fits a word model: for every remake, a probability for each candidate of being the source. The model has 39 columns: 18 word measures, each in two forms (TF-IDF in several weightings, BM25, word pairs, character sequences, latent semantic spaces, word presence), two length measures and one curved term. It is fitted with one family left out at a time, so each pair is scored by a model that never saw it, and with a penalty that pulls its weights towards zero and keeps them stable. It ranks the documented source first for 205 of the 220 pairs.

Only the pairs the word model is unsure of can show anything. Each pair counts for one minus the probability the word model gives its documented source: almost nothing when the words are sure, almost one when they are wrong. Over the 220 pairs these weights add up to 21, which we call 21 open pairs.

The units enter only as their rank among a remake's candidates. For each pair the test first removes from the unit score whatever the word measures can predict. It then asks how far the documented source stands above the candidates the word model still takes seriously: it subtracts the average over the candidates, each counted in proportion to the probability the word model gives it. These differences are added up within each family, and the family sums are added to give a total. Z is that total divided by the square root of the sum of the squared family sums. If the units added nothing, Z would be near 0, and each family's sum would be as likely to be negative as positive. So the registered p is the share of 100,000 random reassignments of the signs that give a total at least as large as the one observed.

A stand-in is a word-only measure that is not part of the word model and is put through the test in the units' place. It holds nothing but words, so a sound test should let few stand-ins pass. The claim that units carry information beyond these word measures needed seven conditions, all fixed beforehand: (1) the test is evaluable, meaning that the word model leaves at least five open pairs, and it passes its own positive control; (2) it is calibrated, meaning that at most 10% of the stand-ins have p below 0.05, and likewise at most 10% of the random word-only measures and of the noisy copies described below; (3) the units' p is below 0.05; (4) with the units added, the word model gives the documented sources more probability on pairs it was not fitted on, which is a gain in held-out log-likelihood; (5) the units' Z is above that of all 74 stand-ins, the largest of which is 2.23; (6) p is below 0.05 at four or more of the eight settings of the presence rule (a threshold of 20, 30, 40 or 50% of scale, by the strongest sentence or the mean of the three strongest); (7) the effect is not confined to pairs the model recognises. A general-purpose sentence-embedding model (all-mpnet-base-v2, with a film taken as the mean of its sentence vectors) was put through the same test in the units' place.

The test's positive control gives the word model a random half of the vocabulary and puts word measures built on the other half in the units' place. They passed in all 12 runs (four measures in each of three splits, Z from 5.2 to 5.7). Planted effects, run with words alone before any unit was analysed, showed that the test finds four times in five an effect of 0.56 standard deviations among a remake's candidates, or of 0.86 when the rest of the unit measure is noise.

The calibration was done with no model, and it shows the test's limits. The designers had calibrated their 31 columns on a shorter list of pairs that the scouting agents had listed from memory. On the final list of 220 pairs, 13 of the 78 stand-ins had p below 0.05, more than the 10% allowed. So before the plan was frozen, and before any unit existed, the stand-in with the lowest p was added to the word model, and the step was repeated until at most 10% of the remaining stand-ins had p below 0.05 and none had p below 0.01. Four additions gave the 39 columns, with 7 of the remaining 74 stand-ins below 0.05 (9.5%) and none below 0.01. The stand-ins helped to choose the columns, so they are not an independent check.

Three checks took no part in choosing the columns. Of 332 random word-only measures, 28 had p below 0.05 (8.4%). Of 3,380 noisy and curved copies of the word measures, 303 did (9.0%). And when pure noise was put in the units' place 2,000 times, p was below 0.05 in 217 of the draws (10.9%) and below 0.01 in 3.3%. So on this list the test's p is too small, and more so the smaller it is. The registered p cannot be read at face value. What protects a claim against noise is condition 5: Z was above 2.23 in 3.55% of the noise draws. It does not protect equally well against every word-only measure. Of the 332 random ones, 7 are above 2.23 (2.1%), the largest at 3.12, which is no more than noise gives. One kind does worse: a TF-IDF on a random half of the words is above 2.23 in 5 of 90 cases (5.6%), 2 of the 60 in the registered draw and 3 of the 30 in a reviewer's second draw. For that reason each model's p on this test is given with a second figure beside it: the share of the noise draws whose Z is at or above the observed one, with the observed value counted as one more draw, so it cannot be smaller than 1 in 2,001. We call it the noise-calibrated p. The noise check and this figure were added after the plan was frozen and before any unit of the remakes was analysed, and they enter no condition. A reviewer's second draw of the random measures gave 11.4% (19 of 166), on the other side of the 10% line of condition 2; the condition was read on the registered draw, as fixed.

Recognition. As in Section 3.6, each model was asked what it was reading. For Holmes: which famous hero a name-free text is about, and which Conan Doyle story it tells. For the remakes: which film a summary describes, and which earlier film it remakes. A pair counts as recognised if the model names the source or identifies either film. Answers were scored by a fixed rule on names and titles and committed before that model's units were analysed.

What is confirmatory. For Qwen3-32B at the primary setting: on Holmes, E1, E2 and E3; on the remakes, heredity and the decision test. Holm's adjustment is applied within each corpus and over the four tests that have a p value. The other three models are replications and are reported whatever they show.

3. Results

3.1 The six confirmatory tests, and what became of version 1's conclusions

One of the six confirmatory tests passes (Table 1). The five confirmatory tests of the two further corpora are in Table 13, with Sections 3.11 and 3.12.

Test	What was predicted	Qwen3-32B	Outcome
E1, identity	Without names, the share of Batman's canon a work carries separates Batman from other hero films (AUC at least 0.80)	AUC 0.36 (95% interval 0.17 to 0.56); 0.37 on openings	Falsified
E2, heredity	Adaptations carry their documented source comic's units more than other comics'	15% of comics beat the source, against 46% by chance; exact p = 0.0016	Supported
Residual test	The units still find the source once word measures are regressed out	p = 0.69; 0.86 with every measure regressed out	Not supported
E3, selection	Units of popular early works spread further	rho = 0.35, p = 0.37	Not detected
Ablation	Switching off the canon lowers the model's recognition of Batman more than matched random units, and more than it lowers other heroes'	Fall of 2.39 in log-odds against 0.02; p = 0.005, 0.005 and 0.0017	Not evaluable under the rule set beforehand
Steering	A blind judge can tell which idea unit was pushed (chance 20%)	17 of 126 (13%), p = 0.98	Not met

Table 1. The six confirmatory tests, all on Qwen3-32B under the new rule. With Holm's adjustment over the five tests that have a p value, E2's is 0.008. A follow-up test of the ablation, written after these results and not one of the six, is in Section 3.8.

Read against version 1, the conclusions are these.

1. **Heredity stands.** It is supported in Qwen3-32B and in each of the other three models, in Llama 3.1 8B with a failed positive control (Sections 3.4 and 3.10).
2. **Words still find the sources as well as neurons do.** The larger model, the full-precision weights and the stricter rule do not change that, and on Batman in no model is anything detectable beyond the words (Section 3.4; the remakes of Section 3.12 differ).
3. **The hint that Llama's neurons add something beyond words is withdrawn.** The test behind it can be passed by words alone. Under a test that none of the word-only measures we tried passes, no model passes on Batman, whether under the new rule or, in the three models where it was run, under version 1's (Sections 2.5 and 3.10).
4. **Identity fails, and more plainly.** The canon share falls from 0.52 to 0.36. Version 1 blamed the scoring rule. Given the words' scoring rule, the units reach 0.62, which is no better than the length of the text. The one exception is Llama 3.3 70B at 0.77 on whole summaries, where length alone gives 0.76. On openings it is 0.65, which is not above its shuffled-label null, so the exception is not established once length is controlled. This is also the model that names Batman for 29 of the 32 works and identifies 15 of them by title (Section 3.3).
5. **The name-free core has gone.** Version 1 found seven name-free units in Qwen3-8B (nine in Llama 3.1 8B) that read like the definition of a superhero. Under a rule that counts only strong activations, Qwen3-8B has none and Qwen3-32B one (Section 3.2).
6. **The canon is mostly names, but less so than version 1 said.** By a blind judgment 38 of the 60 core families that were explained are a name, a place or a word, a share clearly below version 1's 27 of 33 (Section 3.7).

7. **Selection is still not detected,** in a test that could not have detected much (Section 3.5).

Three things are new.

8. **The units can be described, and the descriptions can be tested.** In short texts written to fit a description, 81% of new examples fire the unit strongly and 3% of near misses do, and 46% of units still fire when the description is put without its key words (Section 3.7).
9. **Switching off the canon units lowers the model's recognition of Batman far more than switching off matched random units.** The registered test was not evaluable in Qwen3-32B, and stays so. In Qwen3-8B it could be evaluated and was not met. A follow-up test, written after those results were seen and fixed in the plan before it was run, applies the registered criterion with the model's reply begun for it. It is met in Qwen3-32B and not met in Qwen3-8B, where the effect is again not specific to Batman. It is not one of the six confirmatory tests, and it reads the same texts and units, so it is not a second finding. What it shows is that the Qwen3-32B result holds when the reply is begun for the model (Section 3.8).
10. **We could not show that pushing a unit produces its description.** The same mechanism works on the essay's own neurons, under an easier test (Section 3.8).

Figure 1 separates the effect of the new rule from that of the new models. Under version 1's rule the models at full precision, Qwen3-32B included, give version 1's E1 and E2 numbers again, and version 1's form of the residual test passes in all three (in Qwen3-8B it was 0.089 as published and is 0.015 at full precision). Under the new rule E1 falls and that test fails in all three. So, up to 32B, it was the rule, and not the size of the model, that moved E1 and took the residual test from passing to failing (Section 3.10).




Figure 1. What changed between versions. Identity (E1), heredity (E2) and version 1's form of the residual test for each model: as published in version 1, at full precision under version 1's rule, and under the new rule.

3.2 Presence, the canon, and other film series

Presence. Of Qwen3-32B's 3,276,800 units, 1,812,516 fire strongly in at least one of the 114 works, and 885,060 of those are distinctive, meaning present in at most 3% of ordinary film plots. A typical Batman summary has 140,954 units present with its names and 102,256 without (medians). A third of all units (1,035,162) reach their strongest activation in the supplement of code, chat, other languages, news and reviews, which is what the supplement was added for. Only 4,518 take their scale from the study's own texts. For 82,189 positive poles, 5.0% of neurons, the strongest raw activation is an echo of the other sign regime. The essay puts that figure at about 4%, and under version 1's rule those echoes counted as the unit's own.

The canon. 7,520 distinctive units are present in at least 6 of the 32 Batman works. Merging those that fire strongly on the same sentences gives 4,996 meme families: 74 in the core (29 or more works), 135 common and 4,787 optional. Counted as units, 334 are in at least 23 works and 120 in at least 29 (Figure 2A). The two 8B models have fewer (44 and 59 units in at least 29 works) and Llama 3.3 70B about as many (114).

Remove the names and most of the canon goes with them (Figure 3). On the name-free texts 48 distinctive units are in at least 23 works and 12 in at least 29. E1's canon, the distinctive units present in at least 80% of the works, has 204 units, and exactly one of them is still present in 70% of the name-free works. Qwen3-8B has none, Llama 3.1 8B one and Llama 3.3 70B ten. Version 1 reported a name-free core of 7 units in Qwen3-8B (9 in Llama 3.1 8B) and read it as "close to the standard definition of a superhero" [26]. Under a rule that counts only strong activations, even that has all but gone. Section 3.7 says what the one surviving unit is.

Is that more of a canon than other bodies of films have? Three comparisons could have failed.

- *Random sets of 32 ordinary films*. With the 3% cap a random set cannot have a canon, by construction. Without the cap, Batman has 5,765 units in at least 29 works against a mean of 4,033 for 50 random sets, and the largest of the 50 has 4,492. So Batman's summaries share more units than random films do, but about 70% of what 32 Batman summaries share is what any 32 plot summaries share.
- *Genre sets*. When 32 plots of one genre stand in for the franchise, with base rates taken from the other genres, no drama, comedy, thriller or action set has a single distinctive unit in 23 of its 32 plots, and horror sets average 0.28. Batman has 334. A genre is not a canon by this measure.
- *Other film series*. Batman has more distinctive units in at least 90% of its works than four of the six series have in theirs, about as many as Kamen Rider, and a third as many as Doraemon (Table 2, Figure 2B). At the 72% bar Kamen Rider is ahead of Batman too.

Series	Films	Units in 90% or more of the films	Batman works, random subsets of the same size (mean)
Godzilla	28	89	102
Frankenstein	24	39	116
Dracula	23	38	119
Doraemon	17	327	108
Tarzan	16	50	114
Kamen Rider	15	119	128

Table 2. Batman against six other film series from the same plot dataset, Qwen3-32B, original texts: distinctive units present in at least 90% of a series' films.

So Batman does have a canon in this sense, and so do other series. What the count measures is how uniform a series' summaries are, in names and stock phrases as much as in story. A series with a fixed cast and a formula, as Doraemon has, scores highest. In all four models Doraemon is far ahead of the other series and Kamen Rider comes second.




Figure 2. The canon under the new rule, Qwen3-32B. (A) Units present in at least 6, 23 and 29 of the 32 Batman works: distinctive units on the original texts and on the name-free texts, and all units with no base-rate cap beside the mean for random sets of 32 ordinary films. (B) Distinctive units present in at least 90% of each film series' films, against Batman works in random subsets of the same size.




Figure 3. Which works carry which units. Rows are units chosen by rule and explained (Section 3.7), with the explainer's title. Columns are the 32 Batman works and then the 13 relatives, each in date order. The upper half of a cell is filled where the unit is present in the text as written, the lower half where it is present with every name removed. Titles in black were judged, blind, to describe an idea; titles in grey a particular name or word.

3.3 E1: identity

Without names, Batman's canon does not tell Batman from other masked heroes. For Qwen3-32B the canon share has an AUC of 0.36 against the eight hero films, with a 95% interval of 0.17 to 0.56 (Figure 4). The prediction needed 0.80, so by the criteria registered for version 1 it is falsified, as it is in Qwen3-8B (0.26, and 0.29 on openings) and Llama 3.1 8B (0.39, and 0.40 on openings). Llama 3.3 70B is different, and is taken up below. The score is at or below chance, which means the hero films carry more of Batman's canon than the name-free Batman works do. Superman, Spider-Man, Daredevil and Iron Man each carry more of it than at least 79% of the Batman works. The result is not a matter of length: on the openings, where length no longer separates the two groups, the AUC is 0.37.

The reason is visible in the units. With names present the canon share separates Batman from everything at an AUC of 1.00. Most of those units respond to Batman's names and places, or to the comic-book writing around them (Section 3.7), and the name-free texts delete what they respond to. What is left fires on superheroes in general, and the summaries of superhero films use that vocabulary more than Batman's own do. Against ordinary films and the literary relatives the name-free canon share still separates Batman (AUC 0.96 and 0.98), as in version 1. It tells a superhero story from other stories. It does not tell Batman from Superman.

It was not the scoring rule. Version 1 put this failure down to its scoring rule, because a word-based centroid score reached 0.80. Given the same rule, the units still fall short: the centroid of unit activations has an AUC of 0.62, and on the openings 0.43. Its whole-summary value is no better than text length alone, which reaches 0.76 on whole summaries and 0.45 on openings. The word-based centroid stays ahead at 0.80, and it also holds on the openings (0.73, above its own shuffled-label null). It still does not meet the full prediction, because the lower end of its interval is 0.64 against a required 0.65. With word weights taken from the background plots it reaches 0.83, and 0.77 on openings, and misses on one other clause: it falls by more than 0.05 without the iconography sentences. So words come close to finding a name-free Batman, and the units up to 32B do not. A canon chosen on the name-free texts themselves, a control from version 1, reaches 0.60.

The model itself does better than its canon. Asked which hero a name-free summary is about, Qwen3-32B answers Batman for 21 of the 32 Batman works, and also for 4 of the 8 hero films (Table 3). The log-probability it gives to Batman's name separates Batman works from hero films with an AUC of 0.78, about as well as word counts and far better than the canon share. The two are related: across the 32 works the canon share and that log-probability correlate at rho = 0.63. So the canon units do track the model's recognition of Batman. But the recognition draws on more than the units that count as present.

The largest model is the exception, and it is the one that knows the plots. Llama 3.3 70B's canon share reaches 0.77 (95% interval 0.60 to 0.91), and 0.65 on openings. Length alone gives 0.76 on whole summaries, and the openings figure is not above its shuffled-label null. That misses the bar, the interval and the openings criteria, so the prediction is not met. It is not falsified either, and ten of this model's 215 canon units survive in the name-free works. This is also the model that says a name-free summary is about Batman for 29 of the 32 works and names the exact film for all 69 ordinary plots (Table 3). For the 29 works it names, the canon share separates them from the hero films at 0.81 on whole summaries, a figure that is not length-controlled (length alone gives 0.76). For the three it does not name (the 1943 serial, Batman '66 and Joker), the figure is 0.33. Three works are too few to test this, but the pattern is the one recognition would give: the canon units fire on a name-free text mostly where the model has worked out whose story it is. That would be recognition of summaries it has read, not a name-free essence, and the registered test cannot tell the two apart.




Figure 4. Telling name-free Batman summaries from the eight masked-hero and superhero films, by each model's units, by word counts and by length alone. Large marks are whole summaries with 95% bootstrap intervals; small marks use only the opening of each summary, which is about the same length in both groups. The pre-registered bar is 0.80.

3.4 E2: heredity, and whether neurons add anything to words

Adaptations carry their source comic's units. In Qwen3-32B, on name-free texts, 15% of eligible comics beat the documented source, against 46% expected by chance (exact p = 0.0016; p = 0.0083 when comics are relabelled only within their era). The documented source is the closest eligible comic for four of the nine adaptations and second for two more (Figure 5). The real value is below every placebo target, and 5 of 7 sequels rank their prequel in the top two, so the positive control passes. Heredity is supported, as it was in version 1. Qwen3-8B gives 8% (p = 0.00018), Llama 3.1 8B 14% (p = 0.00047) and Llama 3.3 70B 6% (p = 0.00011). The sequel control passes in Qwen3-8B and Llama 3.3 70B (6 of 7 each) and fails in Llama 3.1 8B (4 of 7), so that model's result is supported with a failed positive control.

Word counts find the sources at least as well. TF-IDF cosine on the same name-free texts gives 11% (p = 0.00031) and ranks the source first for six of the nine adaptations. Word presence gives 17% (p = 0.0018). Qwen3-32B does not pull ahead of words: its 15% is behind TF-IDF's 11%. Llama 3.3 70B has the best figure of any measure at 6%, and its residual test fails like the others.

Nothing is detectable in the neurons beyond these word measures. With the seven word measures regressed out of the neuron inheritance rate, 49% of comics beat the source, which is chance (decision test, exact p = 0.69). With every word and code measure regressed out, p = 0.86. In version 1's two-measure form p = 0.20. The other three models agree (decision test p = 0.62, 0.57 and 0.20). The reverse is not true: with the neurons regressed out of TF-IDF cosine, the words still find the sources (11%, p = 0.0004). On this corpus the words carry the trail and the neurons carry part of it. This is an absence of evidence. With nine adaptations and seven measures regressed out, we have not shown that the test could detect a small contribution.

Version 1 reported that this test passed for Llama 3.1 8B (p = 0.010 to 0.033) and read it as a hint that Llama's neurons add a little beyond words. That reading does not survive. The form of the test used there passes for word-only measures in the neurons' place (Section 2.5). Put through the decision test, no model passes: not under the new rule in any of the four models, and not under version 1's rule in the three it was run on (Section 3.10).




Figure 5. Heredity on name-free texts. (A) For each adaptation, the rank of its documented source among the eligible comics, by each model's units and by TF-IDF word counts. (B) The share of eligible comics that beat the documented source, averaged over the nine adaptations, for units, for the two word measures, and for units after the word measures are regressed out.

3.5 E3: selection

Selection was not detected, as in version 1. In Qwen3-32B the correlation between an early work's popularity and the spread of its units into later works is rho = 0.35 (one-sided p = 0.37). Qwen3-8B gives 0.35 (p = 0.37), Llama 3.1 8B 0.17 (p = 0.56) and Llama 3.3 70B −0.17 (p = 0.83). With 15 early works the test would detect a true correlation of 0.3 about a quarter of the time, so this says little either way.

3.6 Does the model simply recognise the plots?

These models have read Wikipedia, and it shows (Table 3). Given a name-free summary, Qwen3-32B names the exact work for 52 of the 69 ordinary films and 5 of the 8 hero films. It does so for only 4 of the 32 Batman works: it knows it is reading Batman, but not which Batman. Llama 3.3 70B names the exact work for every one of the 69 ordinary films and for 15 of the Batman works.

	Qwen3-32B	Qwen3-8B	Llama 3.1 8B	Llama 3.3 70B
Batman works it says are about Batman	21 of 32	20 of 32	16 of 32	29 of 32
Batman works it identifies by title	4 of 32	2 of 32	2 of 32	15 of 32
Hero films it says are about Batman	4 of 8	4 of 8	1 of 8	1 of 8
Hero films whose own hero it names	4 of 7	3 of 7	5 of 7	7 of 7
Ordinary films it identifies by title	52 of 69	36 of 69	54 of 69	69 of 69
AUC of its log-probability of "Batman", Batman works against hero films	0.78	0.57	0.76	0.90

Table 3. What each untouched model says about a name-free summary.

This matters for how the experiments are read. Had E1 passed, the paper would have had to say that the model recognises Batman's plots, which is a different thing from a name-free essence. In the three models up to 32B it failed, so the question does not arise. In Llama 3.3 70B it comes closest (0.77 on whole summaries against a bar of 0.80, and 0.65 on openings) but is still not met, and Section 3.3 reads that result as recognition of the summaries. For E2 the worry runs the other way: could memorised plots carry the source trail? Qwen3-32B identifies both the adaptation and one of its sources for only one of the nine pairs (The Dark Knight Rises), and that pair is the one where the units place the source worst. Llama 3.3 70B identifies both for five of the nine, and its units place the source no better for those five than for the other four (7% and 6% of comics beat the source). So recall of specific works does not explain the heredity result.

3.7 What the units are, and whether their descriptions hold up

The rule of Section 2.6 chose 241 units in Qwen3-32B and 207 in Qwen3-8B, which has fewer core families. Each got a title and an explanation from an explainer that read its strongest examples, and each explanation was then tested on texts written by someone who had seen nothing else. No unit had to be set aside as not testable out of context.

The descriptions predict where units fire in new text written to fit them. In Qwen3-32B, 81% of the texts that a tester wrote to fire a unit did fire it strongly, against 3% of the near misses and 0.1% of the texts on a distant subject (Table 4, Figure 6). The essay reports 76%, 11% and 1% for its own gallery. The two are not directly comparable: the essay's scale comes from a far larger corpus, so its 30% is harder to reach, and its explanations come from a fuller procedure (Section 4.4). By our reading of the essay's tally, which the essay does not define (a win is more strong new examples than strong near misses), 232 explanations won, 9 tied and none lost. The floor matters here, because a tester writes on the unit's subject and many units share subjects: on texts written for *other* units, a unit fires strongly 6% of the time and an explanation "wins" 17% of the time. So a win is weak evidence on its own, and the rates are the result to read.

	New examples (A)	Idea without the key words (B)	Near misses (C)	Distant (D)	Won / tied / lost	Idea-bound
Qwen3-32B, 241 units	81%	45%	3%	0.1%	232 / 9 / 0	110 (46%)
of which idea units, 126	74%	51%	2%	0.2%	118 / 8 / 0	72 (57%)
of which name or word units, 115	88%	38%	5%	0%	114 / 1 / 0	38 (33%)
On texts written for other units	6%	5%			wins 17%	2.4%
Qwen3-8B, 207 units	85%	40%	4%	0.7%	201 / 6 / 0	73 (35%)
The essay's gallery [10]	76%		11%	1%	164 / 15 / 4	

Table 4. The explanation tests: the share of each kind of test text on which the unit fires strongly (at least 30% of its scale). A unit is idea-bound when at least 3 of its 5 keyword-free texts fire strongly and at most one keyword-reusing near miss does.

About half the units follow their idea when its key words are taken away. Texts that express a unit's idea while using none of its key words fire it strongly 45% of the time, and 110 of the 241 units (46%) are idea-bound, against a floor of 2.4%. On the same texts the unit separates the keyword-free texts from the near misses with a mean AUC of 0.87. The keyword analyst's search terms manage 0.51 and TF-IDF similarity to the unit's examples 0.45. The word measures are at chance by construction, since the texts were written to defeat key words, so this is not a contest that words could have won. What it shows is that for about half of these units (110 of 241) a description predicts firing on text that uses none of the explainer's key words. For the rest, firing mostly stops when the key words go. This is label validation on short AI-written texts, and it supports no claim about units against keyword search. Where a word list could compete, on new examples against near misses, the analyst's search terms separate them almost as well as the unit does (AUC 0.93 against 0.97). For units that detect a name, passing this test means firing on related names the explainer did not list. Nor does it show that units find a story's source better than words do, and Section 3.4 shows that on this corpus they do not.

Batman's canon is mostly names and the comic-book register. The rule explained the 60 core-canon families present in the most works, of 74. A blind judge who saw only the descriptions put 38 of the 60 into the kinds character or name, place, or word or token (63%, 95% interval 52% to 75%). Asked directly, the same judge said 33 of the 60 react to a particular name or word and 27 to an idea. Version 1 put the share higher by hand: 24 of its 33 strongest memes were name or place detectors and 3 detected common words (27 of 33, 82%). The interval here lies below that, which the plan set as the mark of a clearly lower share. So the core is still mostly names, but less so than version 1 said. The titles make the point: "The name 'Gotham' in any sense", "'Dent' in Harvey Dent; Batman villain names", "The Joker and clownish comic figures", "Costumed-superhero name stems, especially Bat- and Wayne". Most of the

rest are of two kinds. Some respond to superhero-comics writing as a genre ("Superhero conventions: first appearance, costume, powers"; "DC Comics titles, teams and issue numbers"). Others sit on the linking word just before a name and fire when the model expects a comic-book character to be named next ("Linking word just before a villain is named"). None of the 60 was judged to be a story pattern, something that happens in a story.

The one unit of the name-free core is L38·N18216−, titled "Superhero comics: heroes versus costumed villains". It is present in 24 of the 32 name-free Batman works, and it passed every test, including all five keyword-free texts. It is a genre unit. It is also present in 5 of the 8 name-free hero films, which is E1's failure in one unit.

The units our rule picked as separating name-free Batman from other heroes mostly react to our own editing. The 40 distinctive units that best tell name-free Batman works from the hero films should have been where Batman's essence showed. Their titles are "Token right after a digit, mostly a space", "Unexpected token straight after a number or code", "Just after a name missing from the text", "Text with a missing word or glitch". Most of them respond to the placeholder codes and the gaps they leave. The typical one is present in 1 of the 32 Batman works as written and in 13 or 14 once the names are replaced, and it is also present in 15 of the 69 name-free ordinary films. They are the hardest set to describe as well: 57% of their new examples fire, against 97% for the core, and 8 of the 9 ties are here. A few do not depend on the editing. One of these is about the story: "Toxins, poisons and toxic substances", present in 10 Batman works with or without the names.

Batman's summaries simply have more names to replace. A name-free Batman text holds a median of 105.5 placeholder codes and a hero film 70.5, and the count of codes alone tells the two groups apart with an AUC of 0.88 on whole summaries (0.74 per word; word count alone gives 0.79), which is higher than any unit or word score in Figure 4. Code tokens are masked (Section 2.1), but the words around a code still show that something was cut. A unit that marks a text as edited is not a meme. This is a limit of the name-free method itself, in version 1 as much as here, and it means that a pass on E1 would have needed checking against it. It did not cause the failures here: the versions of the rule that leave the codes in, or also mask the token after each code, do not change E1, E2 or the residual test (Table 8).

Story ideas appear once the 3% cap is lifted. The 40 commoner units most over-represented in Batman works include "Character taking on a named alter ego", "The word 'vigilante': crime-fighting outside the law", "Villain and hero as stock story roles" and, among the common-tier families, "Superhero's double identity: civilian linked to hero persona". These are the superhero ideas version 1 found in its name-free core, and they are real units whose descriptions pass the tests. The first three are in more than 3% of ordinary film plots, so they are not distinctive. All four also turn up in the hero films, so none picks out Batman.

The units that carry the source trail are ordinary ones. The 20 units drawn from those an adaptation shares with its source comic are grammar and everyday story content: "Pointing back to something just mentioned", "Victim noun right after a violent verb", "Going into a river, lake or floodwater", "Two people acting or bonding as a pair". The 20 drawn from the rest look the same. This fits Section 3.10: heredity is carried by ordinary story material, which words carry too.

Three checks on the descriptions themselves.

- *Near the threshold the descriptions are precise but incomplete.* Presence is decided at 30% of scale, well below the examples an explainer reads. On 1,419 passages from ordinary plots where a unit fires at 30 to 60% of its scale, a blind judge thought the description predicted the firing for 48%. On 1,418 passages where the unit is silent, the judge wrongly predicted a firing for 3%. Coverage rises with strength, from 43% at 30 to 40% of scale to 65% at 50 to 60%. So when a unit is present in a work, its

title is the best single description of why, and about half the time something else set it off. A first round of this check was discarded because the item ids gave the answer away (Section 2.10).

- *A second model family mostly agrees on what kind of thing a unit is.* Qwen3-32B, given the same descriptions as a multiple-choice question, agreed with the Claude judge on whether a unit detects an idea or a name or word for 80% of the units (kappa 0.61 [15]), and on the finer nine-way kind for 55% (kappa 0.45).
- *Checks that need no judge.* In 46% of a unit's strongest examples the peak token is punctuation or a function word, which is what units that anticipate the next word look like. The single best word predicts a unit's activation with a median correlation of 0.36. Held-out strong examples contain one of the explainer's key words 44% of the time, against 12% for random passages.

The larger model's units are not easier to explain. The plan predicted a higher win rate in Qwen3-32B than in Qwen3-8B. It is 96% against 97% (one-sided p = 0.82), so the prediction is not supported. Both are near the ceiling of what a win can show. Two comparisons the plan did not single out point in opposite directions. More of the larger model's units are idea-bound, 46% against 35% (difference 10 points, 95% interval 1 to 19; unadjusted, and not stratified by selection set, where the larger model's sample has twice as many core units). Its explainers also rated its units lower on whether the strongest firings come down to one idea, 6.0 against 6.4 out of 10 (interval −0.71 to −0.10).

Version 1's rewording test, under the new rule. Version 1 rewrote the top sentence of each of its 31 named Qwen3-8B memes to share almost no content word with the original. It reported that 11 units still responded more to the rewording than to any of ten everyday sentences, where mismatched rewordings would give about 5. Read alone by the full-precision model, 24 of the 31 units respond strongly to their own top sentence, and one responds strongly to its rewording: Two-Face's coin. None responds strongly to an everyday sentence. By version 1's own criterion on the new activations, 8 of the 31 survive, against 2.3 expected from mismatched rewordings. So the claim that a few named memes survive rewording holds in its weak form. Under the rule that counts only strong responses, it is one meme.




Figure 6. Testing the descriptions. (A) For each kind of test text, the share on which the described unit fires strongly, for Qwen3-32B and Qwen3-8B, with the essay's reported rates and the rate on texts written for other units. (B) Explanations that won, tied and lost, for each model, its idea units and its name or word units, and for the essay's gallery. (C) The mean AUC with which the unit itself, the keyword analyst's search terms and TF-IDF similarity to the unit's examples tell the keyword-free texts from the near misses.

3.8 Steering and ablation

Steering works on the essay's neurons and not on ours. The steering multiple was chosen on 40 neurons from the essay's public gallery. With a neuron held at 5 times its scale, a blind judge picked its title out of five for 23 of the 40 (against 20% by chance, $p = 2 \times 10^{-7}$). At 1, 2 and 3 times the scale the judge was right for 12, 13 and 18. So the mechanism does what the essay says it does, on the neurons the essay chose to show. The 23 is the best of four strengths tried on those same neurons, and the wrong titles there were drawn from other gallery neurons of any kind.

On the study's units it fails. The judge picked the right title for 17 of the 126 idea units (13%, p = 0.98 against chance), and for 12 of the 115 name or word units (10%). The criterion is not met. Pushing a unit did change what the model wrote: in only 3 of the 241 items were all three continuations the same as the unpushed ones. But the change did not point to the unit. The judge answered "none of these" for 147 of the 241 items. An idea unit's own key words turn up in 24% of the continuations when it is pushed and in 25% when it is not (18% and 21% for the name or word units). Genre units did best, at 7 of 23 (30%, p = 0.16). Qwen3-32B itself, given the same items as a second judge, picked the right title for 21% of the 241 (chance 20%). It agreed with the first judge on 11% of the items (kappa 0.05) and never answered "none of these" on the 40 sham items, so the two judges agree that steering fails and on little else.

We can think of three reasons and cannot tell them apart. The gallery neurons were picked by the essay's authors as clear cases. Ours were picked by rule, half of them from Batman's canon, and most are name pieces, slots before a name and grammar, none of which has much to say in a neutral story opening. The judge's task was also harder here, because the four wrong titles were of the same kind as the right one. And our mechanism is our own guess (Section 4.4). Whatever the reason, the descriptions in Section 3.7 are supported by what the units respond to, and not by what they do when pushed.

Ablation: switching off Batman's canon lowers the model's recognition of Batman, but the registered test is not evaluable. Qwen3-32B is asked which hero a name-free summary is about, with that work's canon units switched off while it reads the summary: a median of 212 units out of 3.3 million. The log-odds that its reply begins with Batman's name fall by 2.39 on average (Table 5, Figure 7). Random sets of as many units, matched on layer, pole and how many name-free Batman works they are present in, lower them by 0.02 on average, and the largest of 200 such sets by 0.12. Sets also matched on how strongly their units fire in these texts do no more (largest 0.11). They still remove less activation than the canon does (60% of it on average, and none of the 200 removes as much), but per unit of activation removed the canon's effect is larger than every set's. The canon's effect is larger than that of every set matched on works in 24 of the 32 works, and larger than every set of both controls in 23. With the canon off, the model's replies name Batman for 13 works where they named him for 20. (The ablation run reads the first 8 tokens of a reply and the recognition probe of Section 3.3 reads 12, which is why that section counts 21: one reply reaches Batman's name after the eighth token.) And the effect is specific on average: the same units switched off in the seven hero films do not lower the log-odds of those films' own heroes (mean −0.07; single films range from a rise of 2.62 to a fall of 1.06; p = 0.0017 for the difference).

	Qwen3-32B	Qwen3-8B
Canon units switched off per work (median)	212	78
Fall in the log-odds of Batman's name, mean over the 32 works	2.39	1.33
200 random sets matched on works: mean, largest	0.02, 0.12	0.03, 0.11
p against those sets	0.005	0.005
200 sets also matched on how strongly the units fire: largest	0.11	0.12
p against those sets	0.005	0.005
Hero films, log-odds of their own hero's name: mean fall	−0.07	0.80
p that the fall is larger for Batman	0.0017	0.28
Replies that name Batman: untouched, then canon off	20, then 13	20, then 16
The canon's fall in log-probability, against the sets' mean	1.24, 0.01	0.44, 0.01
p against the two controls, in log-probability	0.005, 0.005	0.005, 0.005
Untouched replies that do not begin with a name (limit 4)	5	0
Criterion	not evaluable	not met
Follow-up test: the reply begun with "Answer:"		
Fall in the log-odds of Batman's name, mean over the 32 works	1.81	0.89
200 random sets matched on works: mean, largest	0.03, 0.09	0.04, 0.13
p against those sets	0.005	0.005
200 sets also matched on how strongly the units fire: largest	0.11	0.14
p against those sets	0.005	0.005
Hero films, log-odds of their own hero's name: mean fall	−0.59	0.43
p that the fall is larger for Batman	0.0017	0.30
Replies that name Batman: untouched, then canon off	24, then 19	22, then 21
The canon's fall in log-probability, against the sets' mean	0.49, 0.01	0.02, 0.01
p against the two controls, in log-probability	0.005, 0.005	0.29, 0.24
Untouched replies that do not begin with a name (limit 4)	1	0

	Qwen3-32B	Qwen3-8B
Outcome of the follow-up test	met	not met

Table 5. The ablation: the registered test and, under it, the follow-up test, which was written after the registered result was seen and fixed before it was run, with the model's reply begun for it. With 200 random sets the smallest possible p is 0.005. The falls of the two tests are not on the same scale: the registered test scores the name at the very start of the reply, and the follow-up scores it after "Answer:" and a space, which is a different token. Compare each canon with its own random sets.

The registered test passes in neither model. The plan said the test would not count if more than 4 of the 32 untouched replies began with something other than a name, because the score is the probability of the reply's first word. In Qwen3-32B five do (three begin "The story is about", two begin with a placeholder code), so its ablation is not evaluable with this question, and we do not count it as a pass. Qwen3-8B answers with a bare name every time, and its canon's effect is as clear (1.33 against 0.03), but it is not specific to Batman: the hero films' own names fall by 0.80 ($p = 0.28$).

So the numbers suggest that a few hundred units carry much of what lets Qwen3-32B recognise Batman in a name-free summary, and the registered test does not confirm it. The result does not rest on the five replies. In the 27 works whose replies begin with a name, a post hoc look gives a fall of 2.62 against 0.02 for the random sets, again larger than every set.

A follow-up test, with the reply begun for the model. After those results we fixed one more test in the plan, and pushed it before running it (Section 2.7). The question is the registered one, and the model's reply is begun with "Answer:", so that the next word it writes is the name. The texts, the canon units, the random sets and the criterion are the registered run's.

The follow-up test is met in Qwen3-32B and not met in Qwen3-8B (Table 5). In Qwen3-32B all but one of the 32 untouched replies begin with a name; the exception, for *Batman & Robin*, is Batman's name in bold. (One reply, "X-Men" for *Arkham City*, is a team's name and is counted as a name.) With the canon off, the log-odds of Batman's name fall by 1.81 on average over the 32 works, and by 1.95 over the 31 whose replies begin with a name. The random sets lower them by 0.03, and the largest of the 200 by 0.09 (0.11 for the sets also matched on firing). The sets are the registered run's, so they again remove less activation than the canon does (60% of it on average for the second control), and per unit of activation removed the canon's effect is again larger than every set's. The canon's effect is larger than that of every set of both controls in 24 of the 32 works. In five works the log-odds rise with the canon off, most in *Batman & Robin* (2.45) and *Knightfall* (1.99). On average the hero films' own names do not fall. They rise by 0.59 (single films range from a rise of 2.09 to a fall of 0.44; $p = 0.0017$ for the difference with the plan's 10,000 random relabellings, and 0.0013 over every possible relabelling). The replies name Batman for 19 works where they named him for 24: six stop naming him and one, *Lego Batman*, starts. In log-probability, the form the plan first registered, the fall is 0.49 against 0.01, also larger than every set.

This was the expected outcome. The registered numbers were already as clear in the 27 works whose replies began with a name, and the follow-up reads the same model, texts and units. What it adds is that the result holds, by the registered criterion, when the reply is begun for the model and all but one reply begins with a name. It is not a second finding and not one of the six confirmatory tests, and the registered test stays not evaluable. The two runs rank the works alike (the rank correlation of their falls is 0.83), but the sizes of their falls cannot be compared.

Three points about the begun replies. Four replies changed form when the canon was switched off: untouched they began with a name, and with the canon off they began with a name in bold. In each the name in bold is not Batman's, so in none of them does the reply still name Batman where the score can-

not see it. With the five works whose reply with the canon off does not begin with a name left out, the fall is 1.93. Three of the seven hero films are films the model does not name even untouched (it says Batman for two of them and "The Blindfold" for *Daredevil*, which the rule read as a name). Over the four it does name, their own names rise by 0.33. And a begun reply does not say Batman by default: with nothing switched off Qwen3-32B says Batman for 24 of the 32 Batman works, 3 of the 8 hero films and none of the 69 ordinary films, much as without the prefix (21, 4 and none). Qwen3-8B says Batman for 22, 3 and 1, against 20, 4 and 1 without the prefix.

In Qwen3-8B the registered test could be evaluated and was not met, and the follow-up gives the same answer. Every untouched reply begins with a name (one, for *The Dark Knight*, is "The Falcon" followed by a note in brackets, and is counted as a name; counted the other way, 1 of the 32 would not begin with a name). The canon's fall is 0.89, against 0.04 for the random sets and 0.13 for the largest (0.14 for the sets also matched on firing), and it is larger than every set of both controls in 23 of the 32 works. It is again not specific to Batman: the hero films' own names fall by 0.43 ($p = 0.30$), and by 0.70 over the five films whose hero the untouched model names. The model's answers hardly change: its replies name Batman for 22 works untouched and for 21 with the canon off. Where the untouched reply says Batman the fall is 1.53, and the model goes on naming Batman for 20 of those 22, with less confidence. Where it does not, the mean is a rise of 0.52, and two works make it: in *Knightfall* and *Arkham City*, which the untouched model calls Wolverine, the log-odds of Batman's name rise by 9.91 and 6.73. In seven of the other eight such works they fall. The same two works decide the log-probability form. There the canon's mean fall is 0.02, against 0.01 for the random sets ($p = 0.29$ and 0.24), where the registered run gave 0.44 against 0.01 ($p = 0.005$ against both controls). A fall hardly shows in log-probability where the model is already confident, which is why the plan scores in log-odds (Section 2.10), and the two rises cancel the falls in the other works. So in the smaller model the canon's effect is clear against random units in log-odds, seldom changes the answer, and is not specific to Batman.

Where the effect comes from. Four further versions of the registered run were made with 20 random sets each. They are descriptions, not tests, and the canon's effect was the largest of the 21 in every one.

- *Most of the effect is in weak activity.* Switching off only the canon's strong firings, at 30% of scale or more, lowers the log-odds by 0.42. Switching off only its weaker activity lowers them by 1.75. In Qwen3-8B the figures are 0.34 and 1.05. The follow-up test gives the same split, again with 20 sets of each control and the canon larger than every one of them: 0.23 and 1.37 in Qwen3-32B, and 0.18 and 0.67 in Qwen3-8B. On name-free text the canon units seldom fire strongly, and their weaker activity accounts for most of the fall (the two parts do not add up to the whole, 2.39 in the registered run and 1.81 in the follow-up). Counting weak activity does not rescue E1, though: under version 1's rule, which counts it, E1 is at chance (0.52, Table 9).
- *With the names present Qwen3-32B does not need the canon.* On the original texts its fall is 0.28, and it names Batman for 30 of the 32 works before and after. The names reach the answer by other routes as well. In Qwen3-8B the log-odds fall as far as on the name-free texts (1.28), though its replies still name Batman (26 works before, 28 after).
- *Switching the canon off on the question as well as the summary* gives a larger and less specific effect: a fall of 5.34, replies naming Batman down from 20 to 2, and the hero films' own names down by 1.50.




Figure 7. Switching off Batman's canon while a model reads a name-free summary. (A) For each model and test, the mean fall in the log-odds that the reply begins with Batman's name, for the canon and for each random set of the two controls, and the fall in the hero films' own hero names, with the three p values of the criterion. Under each model's registered test is its follow-up test, written after the registered result was seen, with the reply begun for the model. The two tests are not on the same scale, so

compare each canon with its own sets and not one test's fall with the other's. (B) Qwen3-32B's registered test work by work: the fall with the canon switched off for the 32 Batman works and the 7 hero films, with each work's mean over the random sets.

3.9 The same units in other models

Version 1 found that its strongest memes had twins in Llama 3.1 8B, the units there that correlate best with them, at a median correlation of 0.82. It also found that the agreement was mostly about names and collapsed without them. The 0.82 was measured on the sentences the twins were chosen on. The collapse was measured on the name-free texts with the same twin pairs (a median of 0.14, against 0.56 for word-matched units). Here each of the 241 explained Qwen3-32B units has a twin in each other model, chosen on the original sentences and then scored where it was not chosen.

A twin responds to the same description, more weakly. On the texts a tester wrote for the Qwen3-32B unit, its Qwen3-8B twin fires strongly on 33% of the new examples and 3% of the near misses, where the unit itself fires on 81% and 3% (Table 6). The twin's description wins for 61% of the units, against 24% when units are paired with texts written for another unit ($p = 0.0001$), and 19% of twins are idea-bound against 5%. The two Llama models, from another company, give much the same at 8B and at 70B: 28% and 27% of new examples, 3% of near misses, and wins for 52% and 49% of units against 20% and 19%.

On name-free sentences a twin is no closer to its unit than the twin of any equally word-like unit. Twins correlate with their Qwen3-32B unit at a median of 0.61 to 0.62 on the original sentences in all three models. On the name-free sentences that falls to between 0.26 and 0.28. Control units in Qwen3-32B, matched to each explained unit on how well a single word predicts them and on how many sentences they fire in, correlate with their own twins at 0.38 in all three. For the idea units alone the twins and the controls are level (a difference of −0.02, 95% interval −0.07 to 0.02, in Qwen3-8B). The plan asked whether, for idea units, twins beat two nulls: mismatched pairs on the tester's texts, and the word-matched controls on name-free sentences. They beat the first in every model (21%, 21% and 19% of twins idea-bound against 6%, 4% and 3%, $p = 0.0001$) and the second in none, so in no model do they beat both.

	Qwen3-8B	Llama 3.1 8B	Llama 3.3 70B
Twin's correlation with the unit, original sentences (median)	0.61	0.62	0.62
The same on name-free sentences	0.28	0.26	0.27
Word-matched control units and their own twins, name-free sentences	0.38	0.38	0.38
Twin fires strongly on the unit's new examples (A)	33%	28%	27%
On its keyword-free texts (B)	22%	20%	19%
On its near misses (C)	3%	3%	3%
Twin's description wins, against mismatched pairs	61%, 24%	52%, 20%	49%, 19%
Twins that are idea-bound, against mismatched pairs	19%, 5%	18%, 4%	17%, 3%

Table 6. Twins of the 241 explained Qwen3-32B units in three other models. The Qwen3-32B units themselves fire on 81% of their new examples, 45% of their keyword-free texts and 3% of their near misses.

So the same descriptions pick out related units across models and across companies, which is some support for treating a unit's idea as more than an accident of one network. But a twin is a much weaker detector of that idea than the unit it was matched to, and in name-free text the match is no better than shared vocabulary would give, as version 1 found.

3.10 Robustness

All of the checks below were fixed in the plan, except the joint count of cells, which was added after the two 8B models' results were in (Section 2.10). Unless stated they are for Qwen3-32B.

The threshold, the score and the cap. Across 56 settings (a threshold of 20, 30, 40 or 50% of scale; the strongest sentence or the mean of the three strongest; a base-rate cap from 1% to 30%, or none), the name-free canon share never reaches the bar: its AUC against the hero films runs from 0.25 to 0.67, and in no setting is it above its shuffled-label null. Heredity is below 0.05 in 7 of the 8 settings with no cap and in 42 of the 45 settings where it can be evaluated. The residual decision test passes in none of the 8 uncapped settings. With a cap, which does not enter the decision (Section 2.10), it is below 0.05 in 5 of the 37 settings that can be evaluated (6 of 33 in Qwen3-8B, 9 of 33 in Llama 3.1 8B), and in 3, 4 and 10 of them when word presence under the same cap is regressed out as well. Selection is below 0.05 in no setting. For heredity, the residual test and selection the two smaller models give the same picture (Table 7). For identity they differ a little: neither meets the prediction, but the canon share is above its shuffled-label null in 6 of Qwen3-8B's settings (all at the 50% threshold, four of them with a cap; highest AUC 0.79) and in all 8 of Llama 3.1 8B's uncapped settings. Llama 3.3 70B was run at the primary setting only (Section 2.10).

	Qwen3-32B	Qwen3-8B	Llama 3.1 8B
E1: canon share AUC, range over 56 settings	0.25 to 0.67	0.26 to 0.79	0.27 to 0.85
E2: uncapped settings below 0.05	7 of 8	7 of 8	8 of 8
E2: evaluable settings below 0.05	42 of 45	36 of 40	40 of 41
Residual decision test: uncapped settings below 0.05	0 of 8	0 of 8	0 of 8
E3: settings below 0.05	0 of 56	0 of 51	0 of 52

Table 7. The sensitivity grid: threshold by score by base-rate cap. E1 values are whole-summary AUCs, which are not length-controlled.

Llama 3.1 8B's canon share does reach 0.80 in three settings (0.83, 0.85 and 0.83), all with no base-rate cap. With no cap the canon is hundreds to thousands of common units, and a score built from them rises with the length of a text, which on its own gives 0.76. Those settings have no openings version, so length cannot be ruled out for them. At the primary setting, where the openings exist, Llama's canon share is 0.39 on whole summaries and 0.40 on openings.

The cap and heredity. Heredity weakens as the cap tightens. In Qwen3-32B's E2 multiverse of 12,528 specifications, 81% of the uncapped name-free specifications are below 0.05, against 68% at a 5% cap and 29% at a 1% cap. Qwen3-8B goes from 81% to 39% and 10%, and Llama 3.1 8B from 99% to 80% and 29%. The source trail is carried mostly by ordinary story vocabulary and the units that follow it. Rare units carry less of it, but not none. In the sensitivity grid Qwen3-32B's units under a 3% cap still find the sources at the primary threshold and score (20% of comics beat the source, $p = 0.004$), and E2 is below 0.05 in all 9 of the evaluable settings at the 3% and 1% caps. Word presence under the same caps does not find them ($p = 0.06$ and 0.13). Version 1 reported that heredity held in 99.6% of its specifications. Under the new rule the figure for Qwen3-32B is 84% over all specifications: 99.9% on the original texts and 68% on the name-free texts. It is lower because the grid now includes tight caps and high thresholds, where few units are left.

Other versions of the rule, at the primary setting. None of these changes the outcome of E1, E2's test, the residual test or E3 (Table 8). One, leaving the echo regime in, fails the sequel control.

Version	E1 canon share AUC	E2 share	E2 exact p	Residual p	E3 rho
Primary	0.36	0.149	0.0016	0.69	0.35
Scale without the study texts	0.35	0.149	0.0016	0.69	0.31
Scale from the fifth-strongest example	0.37	0.072	0.00005	0.73	0.34
Openings only	0.37	0.120	0.0003	0.40	0.40
Codes left in	0.43	0.124	0.0007	0.87	0.06
Token after each code masked too	0.34	0.109	0.0002	0.60	0.37
Echo regime left in (codes left in too)	0.43	0.219	0.017	0.87	0.13
Weak poles left out (under 25% of the other pole)	0.36	0.124	0.0005	0.65	0.33
Units scaled by the supplement left out	0.37	0.123	0.0009	0.69	0.35

Table 8. Qwen3-32B under other versions of the presence rule. The residual p is the decision test's.

Two rows deserve a note. Leaving the echo regime in, as version 1 did, weakens heredity (22%, against 12% in the row it is to be compared with, codes left in, because this version keeps the codes too) and costs the sequel control a pass (4 of 7 against 5). The echo is noise for this purpose, as the essay's account of it would predict. And taking each unit's scale from its fifth-strongest example, which one freak token cannot set, makes heredity stronger (7%).

What changed a result: the pipeline, the rule or the model. Every primary statistic was also computed under version 1's rule on the new activations (Table 9, and Figure 1 in Section 3.1).

Model	Version	E1 AUC	E2 share	E2 exact p	Residual p, version 1's form	Residual p, decision test	E3 rho
Qwen3-8B	Version 1 as published (4-bit)	0.52	16%	0.0026	0.089		0.25
Qwen3-8B	Full precision, version 1's rule	0.51	14%	0.0003	0.015	0.22	0.29
Qwen3-8B	Full precision, new rule	0.26	8%	0.0002	0.26	0.62	0.35
Llama 3.1 8B	Version 1 as published (4-bit)	0.54	10%	0.0002	0.010		0.00
Llama 3.1 8B	Full precision, version 1's rule	0.53	11%	0.0003	0.035	0.14	−0.04
Llama 3.1 8B	Full precision, new rule	0.39	14%	0.0005	0.20	0.57	0.17
Qwen3-32B	Full precision, version 1's rule	0.52	14%	0.0007	0.023	0.26	0.25
Qwen3-32B	Full precision, new rule	0.36	15%	0.0016	0.20	0.69	0.35
Llama 3.3 70B	Full precision, new rule	0.77	6%	0.0001	0.017	0.20	−0.17

Table 9. The same statistics by model, precision and rule. E1 is the name-free canon share against the hero films. The decision test did not exist in version 1.

Three things follow.

- *Full precision and size changed E1 and E2 little, up to 32B.* Under version 1's rule the full-precision 8B models give nearly the E1 and E2 numbers version 1 published, and Qwen3-32B gives the same again (E1 0.52, E2 14%). The residual test in version 1's form is the exception: in Qwen3-8B it moves from 0.089 as published to 0.015.
- *The fall in E1 comes from the rule.* In these three models the canon share drops from about 0.52, which is chance, to between 0.26 and 0.39 when only strong activations count. Below chance means the hero films carry more of the canon than the name-free Batman works do (Section 3.3).
- *Version 1's residual test passes under version 1's rule in all three models*, Qwen3-8B included ($p = 0.015$, 0.035 and 0.023), and in none of them under the new rule. In Llama 3.3 70B it passes under the new rule as well ($p = 0.017$). The decision test passes in none of the seven cells. This is what a test that leans on common words would do: weak activations follow common words, and the form of the test version 1 used can be passed by a word measure that does the same (Section 2.5).

Counting cells honestly. The six model-by-rule cells of the three models with both rules analyse the same 32 works, so six results below 0.05 are not six independent findings. E2 is below 0.05 in all six. When each relabelling of the comics is applied to all six cells at once, six cells below 0.05 has a probability of 0.0096, so the count adds little to any one cell's p value. Version 1's form of the residual test is below 0.05 in three of the six, which has a probability of 0.046 under the same joint null, and all three are under version 1's rule. The residual decision test is below 0.05 in none.

Trees. As in version 1, a neighbour-joining tree [13] built from the distances between works' meme sets does not recover documented sources in the three models up to 32B. Ranking the 12 comics by distance to each adaptation puts the source at a mean rank of 4.4 in Qwen3-32B, 4.7 in Qwen3-8B and 4.6 in Llama 3.1 8B, against 5.8 by chance ($p = 0.12$, 0.17 and 0.14). TF-IDF distance on the same texts puts it at 2.4 ($p = 0.001$). Llama 3.3 70B is again the exception. Its meme distances put the source at 2.2 ($p = 0.0004$), level with TF-IDF, and even sets of its random units reach 3.2.

The models' distance matrices agree closely with one another (Mantel r [14] = 0.96 to 0.99, and 0.90 to 0.96 with TF-IDF distance held fixed), well above matrices built from random units (0.64 to 0.84 on average). So the models agree about which works are alike. Up to 32B, what they agree on is not the line of descent. Works of the same era sit slightly closer together than works of different eras (ratio 1.03, $p = 0.04$ in Qwen3-32B).

3.11 A second franchise: Sherlock Holmes

The three experiments were run again on the Holmes corpus of Section 2.11: 81 screen works, the 60 stories, and 229 detective films as negatives. Table 10 gives the main figures by model.

The models can tell which texts are about Holmes, and only the largest can usually tell which story. Asked which famous hero a name-free text is about, Qwen3-32B answers Sherlock Holmes for 70 of the 81 screen works. It also answers Holmes for 63 of the 229 detective films, so the answer by itself says little. The log-probability it gives to the name separates the two groups at an AUC of 0.91 within era. Llama 3.3 70B names 65 of the 81 and makes the mistake for only 4 of the 229, and its log-probability separates the groups at 0.96. Asked which Conan Doyle story a name-free adaptation tells, Qwen3-32B gives a documented story for 8 of the 22 adaptations, and Llama 3.3 70B for 18.

Identity comes closer than on Batman, and is still not established in the model that decides the tests. For Qwen3-32B the canon share separates the name-free screen works from the detective films of their era at an AUC of 0.77 (95% interval 0.71 to 0.84), and at 0.73 on the openings. The bar is 0.80, so E1 is not met. Five of its six clauses hold, and it is not falsified. On Batman the same score was 0.36, pooled over all years and against eight hero films. For Qwen3-32B the comparators that use no model do worse here than the units, the reverse of Batman: a TF-IDF centroid reaches 0.62 (0.53 to 0.70), and the num-

ber of placeholder codes alone reaches 0.65. Length works against the franchise here (0.39 for the number of sentences alone and 0.47 for the number of words), so it does not explain the units' score. Pooled over the eras, as the AUC was taken on Batman, the four models give 0.76, 0.64, 0.68 and 0.89, and each verdict is the same. With the names left in, the canon share reaches 0.99 within era. The result is the same with the franchise narrowed to the 74 works in which Holmes appears as a character (0.78), with the detective film that was also a Batman negative left out (0.77), and without the 14,371 units that exceed their scale in some text of this corpus (0.76). On the 46 films alone it is 0.74.

The score rises with the size of the model and passes in the largest one. Qwen3-8B reaches 0.66 (0.63 on the openings), with a canon too small to evaluate (a median of 17 units, where 20 are needed). Llama 3.1 8B reaches 0.699 (0.65 on the openings), just under the 0.70 below which the criteria count the prediction as falsified. Llama 3.3 70B reaches 0.90 (0.85 to 0.94), 0.87 on the openings and 0.88 with the iconography sentences dropped, and meets all six clauses. It is the first time E1 has been met anywhere in this study, and it is met in a replication model, not in the model that decides the tests. The plan had fixed one follow-up for a met E1, because the placeholder codes alone separate the two groups at 0.65. It did not say whether a pass in a replication model calls for it. We ran it for Llama 3.3 70B exactly as fixed, a choice made after that model's E1 was seen and before the follow-up existed: the name-free texts are read again with the token after each code barred from carrying a unit's peak, as well as the code itself. Across the 379 texts that were read (the 370 of Section 2.11, five earlier detective stories that no test uses, and four pages that were set aside), that bars 20,115 more tokens and removes 6.7% of the presences. The AUC is 0.90 again (0.899 against 0.900), so the pass does not come from the tokens that follow the codes.

The score follows what the model can name. In Qwen3-32B the canon share and the log-probability of the hero's name correlate at rho = 0.65 across the 81 works. For the 70 works the model names, the AUC is 0.81 (0.74 to 0.87). For the 11 it does not name it is 0.53 (0.39 to 0.67), which is chance. Llama 3.3 70B shows the same split at a higher level: 0.95 for the 65 works it names and 0.69 (0.55 to 0.83) for the 16 it does not. The plan's rule asked the unnamed works to reach 0.70 with an interval that excludes 0.5. On the texts as first read, the 16 unnamed works reach 0.69 and miss the rule by 0.01. On the texts read again with the token after each code masked, the same 16 reach 0.70 and would meet it. Either way, 16 works at the edge of a threshold cannot carry a claim, and this is a replication model. So the reading is the one Section 3.3 gave for Batman, with better numbers: where a model has read the plots and can say whose story it is, its canon units fire on the name-free text, and this test cannot tell that from a name-free identity. We do not claim that identity holds.




Figure 8. Telling the name-free summaries of the 81 Holmes screen works from the 229 detective films, each work compared with the films of its own era. (A) The canon share of each model's units, then three scores that use no model. Large marks are whole summaries with 95% bootstrap intervals, and small marks use only the opening of each summary. The triangle is Llama 3.3 70B read again with the token after each placeholder code masked as well. The pre-registered bar is 0.80. (B) The same score for the works each model names as Sherlock Holmes and for the works it does not name, with the number of works in each group. The plan asked the works that are not named to reach 0.70. Llama 3.1 8B's 0.699 is under the 0.70 below which the prediction counts as falsified, and Qwen3-8B has too few canon units to be judged.

Heredity holds on a second franchise, for units and for words. For Qwen3-32B, 3.3% of the eligible stories rank above an adaptation's documented story on average, where a random relabelling gives 44% ($p = 0.00001$, the smallest value the sampled null can give). The positive control holds: 8 of the 9 straight adaptations rank a documented story in their top two. Nothing depends on The Hound of the Baskervilles, which accounts for 8 of the 22 adaptations: without it the figure is 3.4% with the same p, and leaving out any one story or any one adaptation gives the same p as well. At all eight rule settings Qwen3-32B gives $p = 0.00001$. At the primary setting the other three models give 5.8%, 5.5% and 5.1% with the same p. In Llama 3.3 70B the positive control fails (5 of 9), so its result is supported with a failed positive control. Words pass too, as they did on Batman: 5.8% for TF-IDF and 8.8% for word presence, both at the same p and with 9 of 9 on the control. The units of Qwen3-32B put the documented story a little higher than TF-IDF does, and no test of that difference was registered. Heredity here does not depend on the model naming the story. For the 14 adaptations whose story Qwen3-32B does not name, the

figure is 3.3% with p = 0.00001. The 16 works that are said only to take elements from stories are found less surely. For the units p is 0.06 in Qwen3-32B and 0.0096, 0.015 and 0.017 in the other three models. For words it is 0.06 with word presence and 0.45 with TF-IDF.

The residual test is reported and settles nothing here. After the word measures are regressed out, the units of Qwen3-32B rank the documented stories below chance (57% of stories above them, against 44% by chance; p = 0.95, and 0.96 when every word measure is regressed out), and no model passes: not at any of the eight settings in the three models run at all eight, and not at the primary setting in Llama 3.3 70B, the only one it was run at (p = 0.89). The plan had found, with words alone, that this regression over-corrects on Holmes and that word-only functions can pass it, so neither a pass nor this null would mean what it should. The question of whether units add to words is the subject of Section 3.12.

Selection is again not detected, and the test could not have settled it. Stories with more page views do not leave detectably more of their units in the 43 screen works that state no source. In Qwen3-32B rho = 0.14 (one-sided p = 0.30), and in Llama 3.1 8B rho = 0.09 (p = 0.36). With only the three covariates used on Batman the correlation in Qwen3-32B is 0.40 (p = 0.025). The plan asked for the fourth covariate, the number of screen works whose article names the story, because popular stories are adapted more often and page views are counted after most of the adaptations exist. We read neither figure as a finding. With the fourth covariate the test would detect a true correlation of 0.3 about one time in three, and the plan fixed in advance that neither outcome would be read as one.

	Qwen3-32B	Qwen3-8B	Llama 3.1 8B	Llama 3.3 70B	Words (TF-IDF)
Screen works the model names as Holmes	70 of 81	65 of 81	59 of 81	65 of 81	
Detective films it names as Holmes	63 of 229	76 of 229	72 of 229	4 of 229	
E1, identity: AUC within era (95% interval)	0.77 (0.71 to 0.84)	0.66 (0.58 to 0.72)	0.70 (0.63 to 0.77); unrounded 0.699, under 0.70	0.90 (0.85 to 0.94)	0.62 (0.53 to 0.70)
E1 on the openings	0.73	0.63	0.65	0.87	0.65
E1 with the iconography sentences dropped	0.74	0.58	0.63	0.88	0.52
Median number of units in the canon	60	17	30	61	
E1 by the six clauses	not met	not evaluable	falsified	met	falsified
E1 for the works the model names: number; AUC	70; 0.81 (0.74 to 0.87)	65; 0.69 (0.62 to 0.76)	59; 0.75 (0.67 to 0.83)	65; 0.95 (0.91 to 0.98)	
E1 for the works it does not name: number; AUC	11; 0.53 (0.39 to 0.67)	16; 0.53 (0.41 to 0.64)	22; 0.56 (0.44 to 0.67)	16; 0.69 (0.55 to 0.83)	
E2, heredity: share of stories ranked above the documented story (0.44 by chance)	0.033	0.058	0.055	0.051	0.058
E2: p	0.00001	0.00001	0.00001	0.00001	0.00001
E2 positive control: straight adaptations with a documented story in their top two	8 of 9	8 of 9	8 of 9	5 of 9 (fails)	9 of 9
E3, selection: rank correlation with page views; p	0.14; p 0.30	0.11; p 0.38	0.09; p 0.36	0.12; p 0.23	

Table 10. Sherlock Holmes by model, on name-free texts. E1 sets the 81 screen works against the 229 detective films of the same era; the word column is a TF-IDF centroid for E1 and TF-IDF cosine for E2. A work is named when the model, asked which famous hero a name-free text is about, answers Holmes. In E2 the p of 0.00001 is the smallest the sampled null can give. E3 uses four covariates.

3.12 Film remakes: do units add to words?

On Batman the residual test found nothing in the units beyond seven word measures (p = 0.69), with nine adaptations and no way of knowing whether it could have detected a small effect. The remakes corpus was built for that question: 220 firmly stated pairs of Indian films from different industries, each remake with a median of 1,544 candidate sources, and a test whose power was measured before any unit was analysed: four times in five it finds a planted effect of 0.56 standard deviations of a measure among a remake's candidates, or of 0.86 if the rest of the measure is pure noise (Section 2.11). Table 11 gives the figures by model.

Three models recognise a minority of these films, and the largest about half. Qwen3-32B gives the right title for 246 of the 887 films of all the kept pairs, and names the earlier film for 82 of the 471 remakes. By the wide definition (it names the source, or identifies either film) it recognises 61 of the 220 primary pairs. Qwen3-8B recognises 35, Llama 3.1 8B 68 and Llama 3.3 70B 110. Llama 3.3 70B gives the right title for 459 of the 887 films.

Heredity holds, and words find the sources at least as well. In the 120 pairs whose summaries are not copied, 1.6% of a remake's candidates rank above its documented source by units on average, where a random relabelling gives 50% (p = 0.0001, the smallest value the sampled null can give). The units rank the source strictly first for 76 of the 120 and in the top ten for 100. In the 100 copied pairs the source is first every time, so the positive control holds. Word measures do the same job at least as well. BM25 puts the source first for 91 of the 120, with 0.5% of candidates above it, and word presence for 77. TF-IDF puts it first for 52, with 0.9% of candidates above it. So taken by themselves the units are a good detector of a remake's source and not a better one than word counts. The two 8B models give the same picture (the source first for 69 and 74 of the 120). Llama 3.3 70B is weaker (55 of the 120).

The word model leaves about 21 pairs open. The word model, scoring each pair without its family, ranks the documented source first for 205 of the 220 pairs. For 178 pairs it gives the source a probability of 0.99 or more, and those pairs can say almost nothing about units. The other 42 are the ones the words leave in doubt. Their weights add up to the 21 open pairs. They include the 15 pairs the word model gets wrong, where the source sits at ranks 2 to 1,676.

Where the words are unsure, the units lean towards the documented source. For Qwen3-32B the family sums add to 25.3 and the statistic is Z = 3.45. Its registered p is 0.00001, the smallest that 100,000 sign flips can give. None of the 2,000 pure-noise draws reaches that Z (the largest is 3.30). The noise-calibrated p is therefore 0.0005, the smallest value 2,000 draws can give; with no draw above, a 95% upper bound on the true figure is 0.0015. None of the 74 word-only stand-ins reaches it (the largest is 2.23), and none of the 332 random word-only measures (3.12). A word measure built afterwards, which leaves names out, does reach it; the checks at the end of this section take that up. With the units added, the word model gives the documented sources more probability on pairs it was not fitted on: the held-out log-likelihood rises by 19.6, from −91.1 to −71.5. The registered p is below 0.05 at seven of the eight rule settings, and Z is above the stand-ins' 2.23 at six. All seven conditions of Section 2.11 hold, so by the wording fixed in the plan the units carry information about which film is the source beyond these word measures. The pairs with copied wording carry none of this, because the words settle them. The whole

sum and all 21 open pairs lie in the 96 pairs whose summaries share under 1% of their five-word sequences, so the plan's rider for a result that sits in copied wording does not apply. Holm's adjustment over the confirmatory tests leaves it far below 0.05 with either p (Table 13).

In the three smaller models the effect holds in the pairs the model does not recognise. In the 159 pairs Qwen3-32B does not recognise, which hold 15.6 of the 21 open pairs, the statistic is Z = 2.84 (registered p = 0.00009; set afterwards against the noise draws of the whole list, 0.004). In the 61 it recognises it is Z = 1.98. Qwen3-8B and Llama 3.1 8B give Z = 2.87 and 3.09 on the pairs they do not recognise.

A simple sentence embedding does not do the same. The sentence-embedding model all-mpnet-base-v2, with each film taken as the mean of its sentence vectors, was put through the test in the units' place. It gives Z = 0.85 (registered p = 0.21, noise-calibrated p 0.27) and lowers the held-out likelihood slightly. With the embedding added to the word measures, the units still pass (Z = 3.55). The embedding is a weak detector of sources here (first for 28 of the 120 pairs that are not copied), so this is a statement about one embedding used in the simplest way, not about embeddings in general. Names may be what holds it back, as they hold back the word model (see the checks at the end of this section).

Two smaller models agree, and the largest does so only for films it recognises. Qwen3-8B (Z = 3.43) and Llama 3.1 8B (Z = 3.73) meet all seven conditions, each with its own recognition split and at all eight settings. They are not a second sample. All four models were tested on the same 220 pairs, with the same candidates and the same word model, so the open pairs are the same for all of them, and, in a count made after the result was seen, the family sums of Qwen3-32B correlate at 0.94 and 0.96 with those of the two 8B models (0.91 and 0.94 over the 31 families with more than a tenth of a pair open). What they show is that the result is not peculiar to one model or one company: it appears in three of the four. Llama 3.3 70B is different. It was run at one setting, and it read 3,926 of the films (Section 2.11). Its Z is 2.72 (noise-calibrated p 0.0065), above the stand-ins' 2.23, with a gain of 7.2. But in the 110 pairs it does not recognise the statistic is Z = 1.23 (registered p = 0.13), and in the 110 it recognises it is 2.49. By the plan's wording its result is "detected at the primary setting only" and "the advantage sits in pairs the model recognises: recall", and no claim is made for it. Conditions 6 and 7 are the two that fail. Condition 6 could not hold, because the model was run at one setting. In a count made after the result was seen, the 94 pairs that no model recognises give Z between 2.75 and 3.50 in the three smaller models and 0.71 in Llama 3.3 70B, so its units are also weaker where recall cannot help. They are weaker on heredity too. It also read a quarter of the films, which changes which units count as optional, so the comparison with the other models is not like for like.

	Qwen3-32B	Qwen3-8B	Llama 3.1 8B	Llama 3.3 70B	Comparators
Primary pairs the model recognises	61 of 220	35 of 220	68 of 220	110 of 220	
Heredity, 120 pairs not copied: share of candidates ranked above the source (0.50 by chance)	0.016	0.014	0.014	0.038	BM25 0.005, TF-IDF 0.009
Heredity: source ranked first	76 of 120	69 of 120	74 of 120	55 of 120	BM25 91 of 120, TF-IDF 52 of 120
Copied pairs: source ranked first	100 of 100	100 of 100	100 of 100	100 of 100	BM25 100 of 100, TF-IDF 98 of 100
Decision test: Z (the largest word-only stand-in reaches 2.23)	3.45	3.43	3.73	2.72	embedding 0.85
Registered p	0.00001	0.00001	0.00001	0.0014	embedding 0.21
Noise-calibrated p	0.0005	0.0005	0.0005	0.0065	embedding 0.27
Gain in held-out log-likelihood	19.6	15.7	17.1	7.2	embedding -0.8
Rule settings with p below 0.05	7 of 8	8 of 8	8 of 8	1 of 1 (one setting run)	
Pairs the model does not recognise: number; Z; p	159; Z 2.84; p 0.00009	185; Z 2.87; p 0.00002	152; Z 3.09; p 0.00001	110; Z 1.23; p 0.13	
Conditions of the plan that hold, of seven	7 of 7	7 of 7	7 of 7	5 of 7 (not 6 or 7)	
With every film read as a candidate: Z	3.59	3.45	3.50	not run	
With the embedding added to the word measures: Z	3.55	3.57	3.87	2.80	

Table 11. The remakes by model: the 220 firmly stated Indian cross-industry pairs. Heredity ranks a remake's candidate films by the units they share with it. The decision test asks whether the units lean towards the documented source where the word model is unsure. The noise-calibrated p is the share of 2,000 draws with pure noise in the units' place whose Z is at least as large; 0.0005 is the smallest it can

be. The gain is the rise in the log of the probability the word model gives the documented sources once the units are added. Comparators: BM25 and TF-IDF for heredity, and a sentence-embedding model put through the decision test in the units' place.

What the effect looks like. The figures in this paragraph and the next were counted from the registered output after the result was seen. The effect sits in the pairs the words get wrong or nearly wrong (Table 12). The largest single contribution is Judwaa 2 and its documented source Hello Brother: the word model ranks the source 54th of the 2,226 films in the pool, and the units rank it 4th. For Khoka 420 and Brindavanam the word model ranks the source 1,676th of 2,975, and the units rank it first. The 15 pairs the word model gets wrong hold 88% of the sum, and every one of them contributes in the source's favour. That does not mean the units rank the source higher than the words do: in nine of the 15 they rank it lower. The test compares the source with the candidates the word model prefers, once the words' share of the unit score is removed. In those 15 pairs the units alone rank the source first three times and in the top ten nine times. The effect is not a better ranking overall. By themselves the units rank the source first for 176 of the 220 pairs, fewer than the word model's 205, and the word model with the units added ranks it first for 206. What changes is how much probability the documented source gets where the words are unsure: its geometric-mean held-out probability over the 220 pairs rises from 0.66 to 0.72.

Remake and documented source	Films ranked	Word model's rank of the source	Units' rank of the source, Qwen3-32B	Units' rank in Qwen3-8B, Llama 3.1 8B, Llama 3.3 70B	Contribution to the sum (25.3 in all)	Recognised by Qwen3-32B	Source is a reference document
Judwaa 2, from Hello Brother	2,226	54	4	4, 9, 19	4.03	no	yes
Khoka 420, from Brindavanam	2,975	1,676	1	2, 7, 30	3.45	yes	yes
Vaseegara, from Nuvvu Naaku Nachav	1,153	7	1	1, 1, 1	2.64	no	yes
Jeena Sirf Merre Liye, from Manasantha Nuvve	994	9	6	11, 15, 19	1.86	yes	yes
Kondapalli Raja, from Khudgarz	955	7	27	26, 33, 62	1.79	yes	yes
Tadakha, from Vettai	2,542	9	9	128, 42, 8	1.73	no	yes
Padaharella Vayasu, from 16 Vayathinile	476	3	4	12, 4, 5	1.42	no	yes
Aegan, from Main Hoon Na	1,534	2	1	1, 1, 1	1.17	yes	no

Table 12. The eight pairs that contribute most to the sum behind Qwen3-32B's Z. Films ranked are the source and its candidates, and a rank of 1 means the source comes first. A reference document is a film whose older summary is among the film plots of the reference corpus that set the units' scales. Most of these sources are ranked high by the units of all four models, with exceptions such as Tadakha's in Qwen3-8B and Kondapalli Raja's in Llama 3.3 70B.

A few families carry it. Most families add nothing, because the words settle their pairs. Of the 29 families whose sum is larger than 0.1 in size, 25 are in the source's favour and 4 against. The five largest hold 54% of the sum, the ten largest 79% and the fifteen largest 93%. A standard measure of that concentration puts it at the equivalent of about fourteen families of equal weight. It does not rest on any one of them: with each of the five largest left out in turn, as the plan asked, Z stays between 3.31 and 3.48. Thirteen of the largest families have to be removed before Z falls below the stand-ins' 2.23. Six pairs have a label a reader could question: a statement that says "reboot", a source reached through an intermediate remake, a pair decided by the third reader, or a year in the film table that contradicts the statement. Judwaa 2, Kondapalli Raja and Tadakha are among them. Without the six, Z = 3.15.




Figure 9. The decision test on the 220 remake pairs. (A) The test's score, Z, for everything put through it: the units of the four models; a sentence embedding, 74 word-only stand-ins, 332 random word-only measures and 16 measures built after the result was seen (13 from words and 3 from the embedding), all in the units' place; and 2,000 draws of pure noise. The dashed line is the largest stand-in (2.23), which the units had to exceed. (B) What each of the 104 families with a sum that is not zero adds to the sum behind Qwen3-32B's Z (25.3 in all), largest first; the other 71 add nothing. Dark bars are the 72 families in which the model recognises no pair, grey bars the 32 in which it recognises at least one.

How far it holds beyond the registered setting. With every film that was read allowed as a candidate, and not only the films of other Indian industries, Z = 3.59. That choice of candidates also passed the stand-in check with words alone. With only the films of the source's industry as candidates, Z = 2.96. That choice does not pass the stand-in check (12 of the 74 stand-ins have p below 0.05 there), so it supports no claim either way. Without the units that exceed their scale in any film, Z = 3.34. With the word

model's penalty set to 10 in place of 3, which also passes the stand-in check, Z = 3.67. With a penalty of 1, or without the hub adjustment, Z = 3.29 and 3.38, but neither setting passes the stand-in check (9 and 10 of the 74 stand-ins have p below 0.05), so neither supports a claim. The secondary sets (pairs within one industry, other cross-industry pairs, loosely worded pairs) do not pass the stand-in check either, and none of them supports a claim. In the loosely worded pairs the units' Z (3.24) is below that of the best word-only stand-in (3.56).

Checks made after the result was seen. Three audits were run by reviewers who were asked to break the result (`study/results/v2/second/audit/`). They are exploratory, and their findings are set out under four heads.

- *When and where a film was made.* Remakes follow their sources closely: a source is 2 years older than its remake at the median (3.5 on average), and the average candidate is 17.6 years older. The test controls for words only, and two properties that are neither words nor units score above the stand-ins in the units' place: the year of release (Z = 2.58) and whether a candidate already belongs to another remake family in the pair list (Z = 3.27). Both have p below 0.05 and are above the stand-ins' 2.23; their gain was not computed. The units do lean towards recent films. With the year gap added to the word model the units give Z = 3.29, with each candidate's industry added 3.21, with the pair-list counts added 3.27, and with year, industry, text length, the number of units a film has, membership of the reference corpus and the pair-list counts all added, Z = 3.04 (Z = 3.43 for Llama 3.1 8B). So none of these removes the result. Together they take about a third of the gain (from 19.6 to 13.7), and the figure to set beside the registered 3.45 is 3.04. The stand-ins were not run again with these controls, so condition 5 was not re-checked, and 3.04 is below the 3.12 that the best random word-only measure reached.
- *Which candidates are allowed.* When the candidates are cut to films released at most five years before the remake, the 33 pairs with an older source drop out, about half of the open pairs are left (10.9) and Z = 1.97. On the same 187 pairs with their whole pools Z = 2.95, and three random pools of the cut size give 1.5, 2.2 and 2.2, so most of that fall seems to come from the smaller pool and not from the year. At 1.97 the result is below the 2.23 that the stand-ins reached on the whole pools, and against noise put through the same cut pools its p is 0.07: with so few candidates the effect cannot be told from noise.
- *The reference corpus.* The reference corpus is the text whose strongest activations set each unit's scale, and it was drawn from the same film table. The plan asked for the result to be split by whether the source's summary is one of its documents; the cut pools and the comparison with the stand-ins were added afterwards. The source is among its documents in 137 of the 220 pairs (62%), and so are 54% of the films read. Pairs with such a source hold 73% of the open pairs and 85% of the sum: Z = 3.06 for them, and 1.83 for the 83 pairs whose source is not one (registered p = 0.035, and 0.079 against the noise draws). The sum per open pair is 1.4 for the first group against 0.7 for the second. Three checks suggest that membership itself is not what the units pick up. As a property of the candidate it stays below the stand-ins' 2.23 in the units' place (Z = 1.94). Adding it to the word model leaves the units at Z = 3.41. And among the films the words find plausible the units rank reference documents lower, not higher. But outside the reference corpus the result is barely tested. With the pools cut to films that are not reference documents, 5.5 open pairs are left, Z = 1.85 and the gain is 0.7 (Llama 3.1 8B: Z = 0.92). On those 83 pairs with their whole pools, the best word-only stand-in (1.92) is above the units' 1.83. The difference between the two groups, 1.4 against 0.7 per open pair, has an interval that includes zero (−0.05 to 1.64), so the result is larger for reference sources and not shown to be confined to them. Most of the evidence still comes from sources whose own summaries helped to set the units' scales. Whether the units do as well for a source whose summary played no part in setting their scales is open.

- *Other word measures*. The 39 columns all count the characters' names as words, and a remake in another industry renames its characters. A third auditor built 16 further measures that use no units: twelve word measures, a score fitted on the 39 columns, and three variants of the sentence embedding. Five of them, all word measures that leave names out, would have passed in the units' place. A TF-IDF over the stems of the words that are not names reaches Z = 3.48, just above the units' 3.45, and the other four reach 2.56 to 3.34. One names-free measure had been tried before the freeze and kept out of the panel. It scored Z = −1.49, but it dropped every word that any film capitalises inside a sentence, which is more than half of the vocabulary (28,748 of 52,955 words), so it was not a fair names-free control. So the units' Z is above every stand-in of the registered panel, which had no names-free member, and it is not above every word-only measure. With each of the 16 added to the word model in turn, the units give Z between 3.11 and 3.56, and with fifteen products of the registered columns added, 3.06. With all of these added together, which makes 85 columns, Z = 3.43. That is above each of 300 noise draws put through the enlarged model and above the largest of the 74 stand-ins under it (2.58), and Llama 3.1 8B gives 3.72. The gain in held-out log-likelihood falls from 19.6 to 11.3 (in Llama 3.1 8B from 17.1 to 7.2). So about half of what the units add to the registered word model is something that words also supply once names are set aside, and the other half is not removed by any word measure we could add.

What qualifies the result. The registered p of this test is too small, by a factor of two at 0.05 and by more below it (Section 2.11), and the calibration condition was met with nothing to spare: 9.5%, 8.4% and 9.0% against a limit of 10%, with a second draw of one of the three at 11.4%. The claim rests on the size of Z against noise and against the 406 word-only measures tested beforehand, not on the p. A word measure built afterwards without names scores as high in the units' place, and with such measures added to the word model the units keep their Z and about half of their gain. It rests on about 21 open pairs and a few families. It is larger where the source's own summary was in the reference corpus, as the check on the reference corpus sets out. The test controlled for words only, and the units were checked against the year of release afterwards. And it puts the documented source first for one more pair: 206 of the 220 against 205.

Test	What was predicted	Qwen3-32B	Outcome
Holmes E1, identity	Without names, the canon separates Holmes's screen works from detective films of their era (AUC at least 0.80)	AUC 0.77 (95% interval 0.71 to 0.84); 0.73 on openings	Not met
Holmes E2, heredity	Adaptations carry their documented story's units more than other stories'	3.3% of stories rank above the documented story, against 44% by chance; p = 0.00001	Supported
Holmes E3, selection	Units of more popular stories spread further into later screen works	rho = 0.14, p = 0.30	Not detected; no claim either way
Remakes, heredity	A remake carries its documented source's units more than its other candidates'	1.6% of candidates rank above the source, against 50% by chance; p = 0.0001	Supported
Remakes, decision test	Where a model of words is unsure of the source, the units lean towards it, under seven conditions	Z = 3.45; registered p = 0.00001; noise-calibrated p = 0.0005; all seven conditions hold	The claim as worded in the plan: information about the source beyond these word measures

Table 13. The five confirmatory tests of the second plan, all on Qwen3-32B at the primary setting. With Holm's adjustment within each corpus, E2's p is 0.00002, the remakes' heredity 0.0001 and the decision test's 0.00002 (0.0002 and 0.0005 with the decision test's noise-calibrated p). Over the four tests that

have a p value they are 0.00004, 0.0002 and 0.00004 (0.00004, 0.0003 and 0.001 with the noise-calibrated p).

4. Discussion

4.1 What the better method changed

Version 1's limitations section, its robustness review and use of the results since publication pointed at its method: small quantised models, a presence rule that counted weak activations, labels read off the corpus, and no causal test. This version addressed each of those, following the essay as far as it publishes its method. The conclusions about Batman did not improve. Where they moved, they moved away from version 1's hint that neurons add to words. That is an absence of evidence, not evidence of absence: word counts already find most of the sources on this corpus, and we have not shown that the residual test, with seven word measures regressed out over nine adaptations, could detect a small contribution.

- Heredity is supported in all four models (in Llama 3.1 8B with a failed positive control), and word counts find the sources about as well. TF-IDF's 11% is ahead of Qwen3-32B (15%) and Llama 3.1 8B (14%) and behind Qwen3-8B (8%) and Llama 3.3 70B (6%), and on Batman in no model do the units add anything once the word measures are regressed out.
- The one result in version 1 that suggested neurons add something to words, Llama's residual test, came from a test that words alone can pass. Under a test that no word-only measure we tried passes, no model adds anything on Batman: not under the new rule in any of the four models, and not under version 1's rule in the three it was run on.
- Without names the canon is at or below chance at telling Batman from other heroes in the three models up to 32B. Version 1 blamed its scoring rule. Given the words' scoring rule, the units do no better than a count of sentences. The 70B model reaches 0.77, short of the bar, and it is the model that names the exact film for every ordinary plot and says Batman for 29 of the 32 Batman works.
- Version 1's name-free core of seven units, which read like a definition of a superhero, was made of weak activations. None is left in Qwen3-8B and one in Qwen3-32B.

Llama 3.3 70B is the exception three times: on identity, on trees, and on version 1's form of the residual test, which it passes under the new rule ($p = 0.017$) where the other three models fail. It is the model that recognises the summaries most completely. It names the exact film for all 69 ordinary plots (the other models 36 to 54) and says Batman for 29 of the 32 name-free Batman works (the others 16 to 21), so on this corpus we cannot separate what its units detect from what the model remembers.

What did improve is the thing the essay is about, the units themselves. A description written from a unit's strongest examples predicts where it fires in new text written to fit it, and nearly half of the units still fire when the idea is expressed without its key words. A second model family largely agrees about what kind of thing each unit is. So the definition this paper started from, that a meme is whatever makes a given neuron fire, can be applied and checked unit by unit against what the unit responds to. That is a real gain over version 1, where a label was a reading of eight sentences. It is half of what the essay's method asks for. The other half, that pushing a unit produces what its description says, failed here.

What two more corpora changed. The same method on two further corpora moved two of these conclusions and left two where they were (Sections 3.11 and 3.12). Heredity is supported again, on a second franchise and on 120 remake pairs, and again words find the sources too: about as well on Holmes, and at least as well on the remakes. Selection is again undetected, by a test too weak to detect it. Identity came closer. Without names the canon of Holmes's screen works separates them from detective films of

their era at 0.77 in Qwen3-32B, where Batman's reached 0.36, and Llama 3.3 70B, a replication model, meets all six clauses of the test at 0.90. In each model the score is higher for the works the model can name (0.69 to 0.95) and near chance, or at the edge of the threshold, for the rest (0.53 to 0.69). What Section 3.3 could only suspect from three works shows more clearly here, with 11 unnamed works in Qwen3-32B and 16 in Llama 3.3 70B: the canon share is higher where the model can say whose story it is. In Qwen3-32B the unnamed works are at chance (0.53). In Llama 3.3 70B they are not (0.69, interval 0.55 to 0.83). The test cannot say whether naming drives the score or both follow from how typical a work is. And on the remakes the units add to the word measures. That is the one question on which a new corpus gave a different answer. On Batman the test found nothing and could not have detected a small effect; on the remakes a test whose power had been measured found one. Section 4.4 lists what qualifies it.

4.2 Why cleaner units did not give a better lineage

Four things stand between a unit that can be described and a unit that is useful for tracing culture, and this study ran into all of them.

The canon is made of names. The units that recur across Batman works and are rare elsewhere respond to Batman's names and to comic-book writing. That is a fair description of what makes a text recognisably Batman, and it is also what any reader or word count would use. Take the names away and what is left is the superhero genre, which Batman shares with the films he is being told apart from.

Removing names leaves a mark. The name-free texts were meant to show what remains of a story without its names. The units our rule picked as best distinguishing name-free Batman mostly respond to the placeholders, and Batman's texts hold more placeholders than the hero films' do: on whole summaries a count of them separates the two groups better than any score built from units or words. This did not cause the failures here, because the versions that leave the codes in or mask more around them give the same results. It limits what a pass would have meant. A future version of this test should use rewritten stories, not redacted ones, as the planned planted-story experiment does.

Presence is decided where descriptions are weakest. The essay's claim is about strong activations, and a description is written from the strongest. Presence in a work is decided at 30% of scale, and there the description accounts for about half of the firings. So a grid of which works carry which memes is noisier than the titles on its rows suggest.

What can be described and what the model uses may be different sets of activity. The essay's working rule is that a neuron's strong activations carry its meaning, and the explanation tests bear that out. In the ablation, most of the fall in the model's answer came from the canon units' activity below 30% of scale, which is the activity the presence rule discards: 1.75, against 0.42 for their strong firings, in the registered run, and 1.37 against 0.23 in the follow-up test. Both are secondary descriptions with 20 random sets, and the first is of a test that was not evaluable. If this holds up, the rule that makes a unit describable throws away signal the model uses. Version 1's rule kept that signal, could not say what it meant, and did no better on identity.

The corpus sets a ceiling of its own. Wikipedia describes a film and the comic it adapts in much the same words, so word counts already find most of the sources (TF-IDF ranks the source first for six of the nine adaptations) and leave little for a neuron to add. The remakes show the same ceiling from the other side. A word model ranks the source first for 205 of the 220 pairs, and what the units add could be seen only in the 21 open pairs it leaves.

4.3 Can creativity be reverse-engineered?

Not from this evidence. What the study supports is narrower, and two more corpora have widened it a little. Inheritance between stories can be measured automatically, from text, with a test that has a known false-positive rate: adaptations carry their sources' material, in Batman, in Sherlock Holmes and in film remakes. A language model's neurons are units that can be named, and the names can be tested and can fail. Switching off the two hundred or so units of Batman's canon lowers Qwen3-32B's recognition of Batman in a summary with no names in it far more than switching off matched random units does. Most of that fall comes from activity below the threshold at which a unit counts as present, where the descriptions were not tested (Section 4.2). The registered test of the effect was not evaluable. A follow-up test, written afterwards and fixed before it was run, is met in Qwen3-32B on the same texts and units and is not met in Qwen3-8B, where the registered test was not met either: the effect there is not specific to Batman.

On the remakes the neurons also carry something about a film's source that a model built from 18 word measures and a simple sentence embedding do not (Section 3.12). That is new, and it is narrow. In a check made after the result was seen, about half of it turned out to be something words also supply once the characters' names are set aside, which the word model of the test did not do. It is one registered test on 220 pairs, of which the words leave about 21 open. It is carried by the pairs the word model gets wrong, in a few families of films. It appears in three models. In the fourth and largest it appears only in the pairs that model recognises. All four were tested on the same 220 pairs. Most of it comes from sources whose summaries helped to set the units' scales. And it does not make neurons the better detector: alone they find fewer sources than the word model does. In the 15 pairs the word model gets wrong, the units alone rank the documented source first three times.

What the study does not support is that neurons find a name-free identity. On Batman a word-count centroid tells name-free Batman from the other heroes at 0.80, and at 0.73 on openings; the canon share reaches 0.36, and 0.37 on openings. On Holmes the canon share does better than the words (0.77 against 0.62) and passes in the largest model, but it follows what each model can name, so it may be the model's memory of the plots. The experiment that could separate the two, on new stories with the wording changed on purpose, is designed and written up as a pre-registration, and has not been run.

4.4 Limitations

The Batman corpus is version 1's. It is one franchise of 32 works, 9 adaptations with 7 source comics, 8 hero-film negatives and 15 early works for the selection test. The texts are 2020s Wikipedia retellings, with no works from 1967 to 1985, and the name-free versions depend on an AI rewriter to find the names. The name-free texts also differ in how much was replaced: Batman's hold more placeholder codes than the hero films', and units can see where a name was cut (Section 3.7). A pass on a name-free comparison between the two groups would have to be checked against that difference. The checks that leave the codes in, or also mask the token after each code, do not change E1, E2 or the residual test (Table 8). Wikipedia describes a comic and the film that adapts it in much the same words, so on this corpus word counts leave little for any unit to add. A better method cannot fix any of this.

This is a second analysis of the same works. The plan was fixed before the new models read a study text, but it was written knowing how version 1 came out. Where the two versions agree, that is the same 32 works giving the same answer twice, and the two 8B models are near-repeats of version 1's.

The two further corpora have limits of their own. They are Wikipedia summaries again, and every label in them (which story a screen work adapts, which film a film remakes) comes from AI readers of Wikipedia's wording. No human read a pair, and six of the remake pairs carry a label a reader could question (Section 3.12). The models have read many of these plots: Qwen3-32B names Holmes for 70 of

the 81 screen works and recognises 61 of the 220 remake pairs. The Holmes name-free texts were made by the same rewriter and carry the same placeholder codes, which alone separate the franchise from the detective films at 0.65. The remakes result is a statement about one word model, built from 18 word measures, and 220 Indian film pairs. The secondary sets were not calibrated and support nothing. The test's p values are too small, by a factor of two at 0.05 and by more below it. Its calibration condition was met at the margin, and its stand-ins were all word measures: the year of release, which is not a word measure, scores above all of them in the units' place, and so does a count of how many relatives a candidate has in the pair list. The units were checked against both only afterwards. The word model counted names as words, and a word measure built after the result was seen, which leaves names out, would also have passed in the units' place; with such measures added, the units keep their score and about half of their gain. The result rests on about 21 open pairs and a few families, and most of it comes from sources whose summaries were documents of the reference corpus, so it has not been shown for films whose summaries played no part in setting the units' scales. Llama 3.3 70B, the model that recognises the most films, shows it only in the pairs it recognises. None of the explanation, steering or ablation tests was repeated on these corpora, so nothing is known about what the units behind the remakes result respond to.

The scale is smaller than the essay's. A unit's scale is one maximum over about 48 million tokens, where the essay had 100 million to 10 billion, so "30% of the strongest example" is somewhat easier to reach here. The reference corpus also holds a little Batman text (a few Wikipedia articles about Batman spin-offs), which can set the scale of a unit for Batman's names. The reference pass reads documents in padded batches at 16-bit precision, which changes activations slightly from a single reading. Section 3.10 varies the scale and the threshold.

The explanations are one AI reading. The essay's explanations come from agents that probe, ablate and steer for themselves. Ours come from an explainer that read the strongest examples once and ran nothing. The testers' texts are short, AI-written and read without context. Every agent in the loop, judges included, belongs to one model family. Qwen3-32B repeated the kind judgments (Section 3.7) and the steering judgments (Section 3.8). On steering it agreed with the Claude judge at about the rate chance would give, so it is not a check on that judge. No human has audited any of it. The tests support claims about these labels on these units. They are not a test of neurons against keywords, embeddings or an LLM reading the text, which is what the planned planted-story experiment is for.

The causal tests rest on our own choices. The essay does not publish how it steers, so the mechanism here (holding a unit at a multiple of its scale at every position) is ours, and the multiple was the largest of four tried. Steering failed on the study's units, and we cannot say whether that is the units, the judge's harder task or the mechanism. The ablation switches units off on the summary's tokens only and scores one question in one wording. In Qwen3-32B that wording drew five replies that do not begin with a name, one more than the rule allowed, so the registered test is not evaluable. A follow-up test with the reply begun for the model is met in Qwen3-32B and not met in Qwen3-8B, where the registered test was not met either. It was written after the registered result was seen, though fixed before it was run, and it reads the same model, texts and units. It was expected to pass, and it shows only that the Qwen3-32B result holds when the reply is begun for the model. The ablation also switches off about 212 units together: it does not show that any one unit is used, and most of the fall comes from activity below the presence threshold (Section 4.2). So the clearest causal result in the paper is still not a confirmed one.

The 3% cap favours names. Ordinary story patterns are commoner than 3% in film plots, so a canon of distinctive units is tilted towards names and rare words by construction. The units chosen without the cap (Section 3.7) and the uncapped analyses are there to show the other side.

Selection is untested in any useful sense. With fifteen early works the test has about a one-in-four chance (27% power) of detecting a moderate effect (a true correlation of 0.3). On Holmes, with 60 stories and a control for how often a story has been adapted, it has about one chance in three.

4.5 Next

Version 1 ended with a list of experiments designed to find out whether neurons see more than words. One of them, the planted-story experiment with its head-to-head on accuracy and cost, has since been written up as a pre-registration in the repository's `preregistration/` folder. It is committed and can still change until its freeze. The others were deferred and are not pre-registered. None has run. This version does not replace them, and its results sharpen what they need to show. The 70B result adds a reason for them: a model that has read the summaries can recognise them, and only stories written after its training can show what its units detect without that help. The remakes result adds another: there is now an effect to look for where neither the model's memory nor the setting of the scales can help.

- **Planted stories.** New stories with chosen ideas written in, matched stories without them, and decoys that use an idea's words without the idea. This is the direct test of whether a unit follows an idea when the words change, with a control twin for every story. The explanation tests here are a weaker version of it, on labels and short texts.
- **A head-to-head on accuracy and cost.** Neurons against keywords, embedding vectors and an LLM reading the texts. Section 3.3 gives a first hint of how that may go: asked directly, the model tells Batman from other heroes better than its own canon units do.
- **Lineages where wording cannot carry the signal.** The remakes of Section 3.12 are a first step: adaptations across languages, where the names change by themselves. The wording often does not: in 100 of the 220 pairs the two summaries share copied text, and words still find the source for 205 of the 220 pairs. What they leave open is the same test on films whose summaries played no part in setting the units' scales, with the year of release among the controls from the start, and then loose adaptations and stories rewritten in stages.
- **Batman's family across culture, and mutation and selection (deferred).** These need a larger and more varied lineage than 32 summaries.

The pre-registration names the 4-bit 8B models and version 1's rule as primary. This version shows that a larger model at full precision under a stricter rule gives the same answers on the experiments, and that the stricter rule is the one under which a unit's description can be tested. Whether to amend the pre-registration before any of it runs is a decision for its first author, and it has not been taken here.

References

1. Dawkins R. 1976 *The selfish gene*. Oxford, UK: Oxford University Press.
2. Aunger R (ed.). 2000 *Darwinizing culture: the status of memetics as a science*. Oxford, UK: Oxford University Press.
3. Edmonds B. 2005 The revealed poverty of the gene-meme analogy: why memetics per se has failed to produce substantive results. *J. Memetics* **9**.
4. Mesoudi A, Whiten A, Laland KN. 2006 Towards a unified science of cultural evolution. *Behav. Brain Sci.* **29**, 329–383.
5. Tehrani JJ. 2013 The phylogeny of Little Red Riding Hood. *PLoS ONE* **8**, e78871.
6. da Silva SG, Tehrani JJ. 2016 Comparative phylogenetic analyses uncover the ancient roots of Indo-European folktales. *R. Soc. Open Sci.* **3**, 150645. doi:10.1098/rsos.150645
7. Goh G, Cammarata N, Voss C, Carter S, Petrov M, Schubert L, Radford A, Olah C. 2021 Multimodal neurons in artificial neural networks. *Distill* **6**, e30.
8. Gurnee W, Horsley T, Guo ZC, Kheirkhah TR, Sun Q, Hathaway W, Nanda N, Bertsimas D. 2024 Universal neurons in GPT2 language models. *Trans. Mach. Learn. Res.*

9. Huh M, Cheung B, Wang T, Isola P. 2024 The platonic representation hypothesis. In *Proc. 41st Int. Conf. Machine Learning*.
10. Cammarata N. Neural networks are already clean. Goodfire. already-clean.goodfire.com (accessed 7 November 2026).
11. Qwen Team. 2025 Qwen3 technical report. arXiv:2505.09388.
12. Grattafiori A *et al.* 2024 The Llama 3 herd of models. arXiv:2407.21783.
13. Saitou N, Nei M. 1987 The neighbor-joining method: a new method for reconstructing phylogenetic trees. *Mol. Biol. Evol.* **4**, 406–425.
14. Mantel N. 1967 The detection of disease clustering and a generalized regression approach. *Cancer Res.* **27**, 209–220.
15. Cohen J. 1960 A coefficient of agreement for nominal scales. *Educ. Psychol. Meas.* **20**, 37–46.
16. Marti L, Wu S, Piantadosi ST, Kidd C. 2023 Latent diversity in human concepts. *Open Mind* **7**, 79–92.
17. Heylighen F, Chielens K. 2009 Evolution of culture, memetics. In *Encyclopedia of complexity and systems science* (ed. RA Meyers). New York, NY: Springer.
18. Quian Quiroga R, Reddy L, Kreiman G, Koch C, Fried I. 2005 Invariant visual representation by single neurons in the human brain. *Nature* **435**, 1102–1107.
19. Chavalarias D, Cointet J-P. 2013 Phylomemetic patterns in science evolution: the rise and fall of scientific fields. PLoS ONE **8**, e54847. doi:10.1371/journal.pone.0054847
20. Kuhn T, Perc M, Helbing D. 2014 Inheritance patterns in citation networks reveal scientific memes. *Phys. Rev. X* **4**, 041036. doi:10.1103/PhysRevX.4.041036
21. Barbrook AC, Howe CJ, Blake N, Robinson P. 1998 The phylogeny of The Canterbury Tales. *Nature* **394**, 839. doi:10.1038/29667
22. Chaturvedi S, Srivastava S, Roth D. 2018 Where have I heard this story before? Identifying narrative similarity in movie remakes. In *Proc. 2018 Conf. North American Chapter of the Association for Computational Linguistics: Human Language Technologies*, vol. 2, pp. 673–678. doi:10.18653/v1/N18-2106
23. Hatzel HO, Biemann C. 2024 Tell me again! A large-scale dataset of multiple summaries for the same story. In *Proc. 2024 Joint Int. Conf. Computational Linguistics, Language Resources and Evaluation* (LREC-COLING 2024), pp. 15732–15741. aclanthology.org/2024.lrec-main.1366
24. Choi D, Huang V, Meng K, Johnson DD, Steinhardt J, Schwettmann S. 2024 Scaling automatic neuron description. Transluce. transluce.org/neuron-descriptions (accessed 20 October 2026).
25. Movva R, Peng K, Garg N, Kleinberg J, Pierson E. 2025 Sparse autoencoders for hypothesis generation. In *Proc. 42nd Int. Conf. Machine Learning*. arXiv:2502.04382.
26. Coogan P. 2006 *Superhero: the secret origin of a genre*. Austin, TX: MonkeyBrain Books.
27. Jha R, Zhang C, Shmatikov V, Morris JX. 2025 Harnessing the universal geometry of embeddings. arXiv:2505.12540. doi:10.48550/arXiv.2505.12540

Data, code and AI use

Data and code. Everything is in the study folder, `study/`, of github.com/hammer-mt/phylomemetics. The code for this version is in `study/v2/`, its results in `study/results/v2/`, and the analysis plan in `study/v2/PLAN.md`. Version 1's code and results are unchanged beside them, and version 1 of the paper is in `study/paper/`. The tables in this paper are written from the committed results by `study/v2/analysis/paper_tables.py`, and the figures by the scripts in `study/v2/figs/`. Every explanation, every test text and every judge's verdict is committed, with the prompts the agents were given. The reference corpus and supplement are built from pinned public datasets by `study/v2/build_reference.py` and `study/v2/build_supplement.py`, and every document is listed in the results. Raw activations are not stored; the passes can be re-run with the scripts on a rented GPU. The rented machines for this version were billed at $107 ($106 of GPU time and $1 of disk), of which $34 was for the two further corpora (the record is in `study/results/v2/gpu_cost.json`), of a budget of $200. The code is under the MIT licence. Plot summaries and texts derived from them come from English Wikipedia and remain under CC BY-SA 4.0.

The two further corpora. Their plan, code and data are in `study/v2/second/` and `study/data/second/`, and their results in `study/results/v2/second/`. Tables 10, 11 and 13 are written from `study/results/v2/second/paper_tables.md`, which `study/v2/second/paper_tables.py` makes from the committed results. Table 12 is written from the models' result files, and Figures 8 and 9 are drawn by `study/v2/figs/holmes.py` and `study/v2/figs/remakes.py`. The plan (`study/v2/second/PLAN.md`) was committed and pushed (commit `9b0099d`, 22:09 UTC on 8 November 2026) before any model read a new text as a study work. The

reference corpus already held older summaries of 112 of the 310 screen works and detective films of the Holmes corpus and of 479 of the 887 films of the remake pairs. Section 16 of the plan logs every change made afterwards. The checks of Section 3.12 that are marked as made after the result was seen are exploratory, and their files in `study/results/v2/second/audit/` say so.

Pre-registration. The three experiments were specified, with falsifying results, before version 1 ran them. For this version the analysis plan was committed and pushed to the repository (commit `1f32fd1`, 02:55 UTC on 7 November 2026) before any of its models read a study text, so the repository's history records the order. The plan was reviewed beforehand by independent AI reviewers asked to find what was wrong with it. Section 18 of the plan logs the changes made after the freeze, each with its reason and with what was known at the time. The planted-story experiment that version 1 promised is written up as a pre-registration in `preregistration/`, committed and open to change until its freeze. It has not run, and this version does not replace it.

Authors' contributions. Mike Taylor conceived the study and its theoretical framing, chose the Batman case and directed the work. For this version he asked for the method to be aligned with Cammarata's essay and for the weaknesses of version 1 to be fixed, and provided the GPU budget. He then asked for a second corpus, and chose to run both of the candidates that the scouting put forward. Claude wrote the plan and the code for this version, ran the models and the analyses, and drafted the paper.

AI use. Claude is an AI model made by Anthropic, and is credited as an author for the contributions above. AI agents of the same model family also played every role in the explanation tests (explainer, tester, keyword analyst, kind judge, coverage judge and steering judge), each seeing only its own prompt, and carried out the adversarial reviews of the plan and the fact-check of this paper. For the two further corpora, agents of the same family also read Wikipedia's wording to label the pairs, designed and calibrated the remakes test, reviewed the plan and the code, and audited the result. Qwen3-32B repeated the kind and steering judgments as a second model family. No human has audited the explanations or the judges' verdicts. The items and answer keys are committed so that an audit can be done.

Competing interests. None declared.